

PROPOSED STORM SEWER PIPE SCHEDULE

PIPE NO.	PIPE LOCATION				DESCRIPTION	DIAMETER (IN)	LENGTH (FT)	TRENCH BACKFILL (CY)
	FROM STATION	OFFSET	TO STATION	OFFSET				
1	102+13	12' LT	102+13	15' LT	RCCP CLASS IV TYPE 1	12	3	0.5
3	98+07	10' LT	98+07	15' LT	RCCP CLASS IV TYPE 1*	12	5	0.5
4	100+98	7' RT	101+19	9' RT	RCCP CLASS V TYPE 4	21	24	48
5	101+13	30' RT	101+19	9' RT	RCCP CLASS III TYPE 2	12	21	14
TOTAL								63

* USE DUCTILE IRON PIPE, CLASS 50 IF WITHIN 10 FT OF A WATERMAIN.

CHAIN LINK FENCE SCHEDULE

STATION	CHAIN LINK FENCE REMOVAL (FEET)	CHAIN LINK FENCE - 4' (FEET)	CHAIN LINK FENCE - 6' (FEET)
98+69, 32' LT	35	46	
99+16.3, 15' LT	30		20
99+12, 23' RT	20	20	
100+87, 15' LT	38	24	
100+81, 23' RT	30	30	
TOTAL	153	120	20

EXISTING STORM SEWER PIPE REMOVAL SCHEDULE

FROM STATION	OFFSET	TO STATION	OFFSET	PIPE DIAMETER (IN.)	PIPE LENGTH (FT.)
100+98	6' RT	101+17	32' RT	6	25
100+98	6' RT	101+21	9' RT	21	21
102+13	13' LT	102+13	16' LT	12	3

PLOT SCALE: \$SCALE\$ SHORT \$

FILE NAME =	DESIGNED -	REVISED -	COOPER CIVIL ENGINEERING, LTD. 1322 ROSALIE STREET EVANSTON, ILLINOIS 60201 (847)864-5343	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES				F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
\$FILEL\$	DRAWN -	REVISED -							08-00251-00-BR	COOK	118	18	
USER NAME = \$USER\$	CHECKED -	REVISED -			SHEET NO. OF SHEETS STA. TO STA.				CONTRACT NO.63817				
PLOT DATE = \$DATE\$	DATE -	REVISED -							ILLINOIS FED. AID PROJECT				