

EXISTING CURB & GUTTER AND CURB REMOVAL SCHEDULE

STATION FROM	STATION TO	CURB & GUTTER REMOVAL (FT.)	CURB REMOVAL (FT.)
98+06.1, 9' LT	99+14.0, 8' LT	120	
98+06.1, 17' RT	99+11.7, 15' RT	115	
100+87.2, 10' LT	101+20.1, 15' LT	34	
101+20.1, 15' LT	101+40.0, 16' LT	20	20
101+40.0, 16' LT	102+15.7, 12' LT	96	
102+13.0, 26' LT	102+27.2, 31' LT		16
100+85.0, 13' RT	101+13.0, 13' RT	28	
101+13.0, 13' RT	101+45.0, 14' RT	48	
101+45.0, 14' RT	102+15.1, 19' RT	75	
TEMPORARY DRIVE	102+88, 177' LT	81	40
TOTAL		617	76

PROPOSED CURB & GUTTER AND CURB SCHEDULE

STATION		COMBINATION CONCRETE CURB AND GUTTER TYPE B-6.12 (FEET)	CONCRETE CURB TYPE B (FEET)
FROM	TO		
97+90, LT	99+19, LT	129	
97+97, RT	99+14, RT	117	
100+86, LT	102+36, LT	147	50
100+82, RT	102+16, RT	135	
TEMPORARY DRIVE	102+88, 177' LT	35	63
TOTAL		563	113

PLOT SCALE: \$SCALE\$ SHORT \$PEN\$