

# SUMMARY OF QUANTITIES

MAIN STREET				
CODE NO.	PAY ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE 0005
20101200	TREE ROOT PRUNING	EACH	1	1
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	90	90
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	4	4
25000500	PHOSPHOROUS FERTILIZER NUTRIENT	POUND	4	4
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	4	4
25200110	SODDING, SALT TOLERANT	SQ YD	90	90
25200200	SUPPLEMENTAL WATERING	UNIT	5	5
28000510	INLET FILTERS	EACH	4	4
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	513	513
40600300	AGGREGATE (PRIME COAT)	TON	13	13
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	10	10
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	216	216
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	90	90
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	435	435
42001300	PROTECTIVE COAT	SQ YD	160	160
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	50	50
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	5,130	5,130
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	65	65
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	161	161

MAIN STREET				
CODE NO.	PAY ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE 0005
44201798	CLASS D PATCHES, TYPE I, 13 INCH	SQ YD	100	100
44201803	CLASS D PATCHES, TYPE II, 13 INCH	SQ YD	150	100
44201807	CLASS D PATCHES, TYPE III, 13 INCH	SQ YD	150	150
44201809	CLASS D PATCHES, TYPE IV, 13 INCH	SQ YD	200	200
50406100	FRAMES AND LIDS, TYPE 1, CLOSED LID	EACH	3	3
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	161	161
67100100	MOBILIZATION	L SUM	1	1
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1
70300100	SHORT TERM PAVEMENT MARKING	FOOT	720	720
70300210	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS	SQ FT	45	45
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	295	295
* 78000100	THERMOPLASTIC PAVEMENT MARKING-LETTERS AND SYMBOLS	SQ FT	45	45
* 78000200	THERMOPLASTIC PAVEMENT MARKING-LINE 4"	FOOT	2,700	2,700
* 78000650	THERMOPLASTIC PAVEMENT MARKING-LINE 24"	FOOT	25	25
Z0004510	HOT-MIX ASP-ALT DRIVEWAY PAVEMENT, 3"	SQ YD	15	15
X2800510	INLET FILTER CLEANING	EACH	4	4
X6030310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	20	20

\* DENOTES SPECIALTY ITEM