

SUMMARY OF QUANTITIES						
CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QTY.	RDWY 0004	TRAFFIC SIGNALS 0021	WAUBONSEE COMMUNITY COLLEGE 0021
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	78	78		
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	17	17		
20101700	SUPPLEMENTAL WATERING	UNIT	31	31		
20200100	EARTH EXCAVATION	CU YD	2,075	2,075		
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	680	680		
20800150	TRENCH BACKFILL	CU YD	742	742		
* 21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	10,286	10,286		
* 25000210	SEEDING, CLASS 2A	ACRE	1.8	1.8		
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	192	192		
* 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	192	192		
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	192	192		
* 25100630	EROSION CONTROL BLANKET	SQ YD	9,770	9,770		
* 25200110	SODDING, SALT TOLERANT	SQ YD	2,057	2,057		
* 28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	4,038	4,038		
* 28000305	TEMPORARY DITCH CHECKS	FOOT	240	240		
* 28000400	PERIMETER EROSION BARRIER	FOOT	4,004	4,004		
28000500	INLET AND PIPE PROTECTION	EACH	2	2		
28000510	INLET FILTERS	EACH	18	18		
28100107	STONE RIPRAP, CLASS A4	SQ YD	32	32		
28200200	FILTER FABRIC	SQ YD	32	32		
† 30300108	AGGREGATE SUBGRADE IMPROVEMENT 8"	SQ YD	1,660	1,660		
† 30300112	AGGREGATE SUBGRADE IMPROVEMENT 12"	SQ YD	4,606	4,606		
35501303	HOT-MIX ASPHALT BASE COURSE, 4 3/4"	SQ YD	1,549	1,549		
35501318	HOT-MIX ASPHALT BASE COURSE, 8 1/2"	SQ YD	2,647	2,647		
35600665	HOT-MIX ASPHALT BASE COURSE WIDENING, 4 3/4"	SQ YD	410	410		
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	1,599	1,599		
40600300	AGGREGATE (PRIME COAT)	TON	32	32		
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	9	9		
40600827	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	423	423		
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	84	84		
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	20	20		
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	784	784		
42001300	PROTECTIVE COAT	SQ YD	314	314		
44000100	PAVEMENT REMOVAL	SQ YD	1,184	1,184		
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SQ YD	3,491	3,491		
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	198	198		
44002216	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 4"	SQ YD	86	86		
44003100	MEDIAN REMOVAL	SQ FT	386	386		
44004250	PAVED SHOULDER REMOVAL	SQ YD	1,910	1,910		
44201741	CLASS D PATCHES, TYPE II, 8 INCH	SQ YD	12	12		
44201747	CLASS D PATCHES, TYPE IV, 8 INCH	SQ YD	74	74		
48101500	AGGREGATE SHOULDERS, TYPE B 8"	SQ YD	529	529		
48203007	HOT-MIX ASPHALT SHOULDERS, 2 1/2"	SQ YD	186	186		
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	1,347	1,347		
54213453	END SECTIONS 18"	EACH	2	2		
54213465	END SECTIONS 30"	EACH	1	1		
† 54260311	TRAVERSABLE PIPE GRATE	FOOT	26	26		
550A0050	STORM SEWERS, CLASS A, TYPE 1 1/2"	FOOT	162	162		

* DENOTES SPECIALTY ITEM
† DENOTES SPECIAL PROVISION

PATRICK ENGINEERING
 PATRICK ENGINEERING INC.
 4970 VARSITY DRIVE
 LISLE, IL 60532
 patrickengineering.com

USER NAME = #USER#	DESIGNED - MJP	REVISED - 4/16/2013
PLOT CONFIG = #PLTDRVS#	DRAWN - MJP	REVISED - 5/7/2013
PLOT SCALE = #SCALESHORT#	CHECKED - JAH	REVISED - 5/29/2013
PLOT DATE = #DATE#	DATE - 3/25/2013	REVISED -

**STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION**

**ILLINOIS ROUTE 47 AT WAUBONSEE DRIVE
 SUMMARY OF QUANTITIES**

SCALE: N/A SHEET 001 OF 3 STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
326	11-00001-00-CH	KANE	55	4
CONTRACT NO. 63829				
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				