

SIGN INFORMATION						SIGNING SCHEDULE			
STATION	LOCATION	OFFSET LT RT	SIGN NUMBER	WIDTH (FT)	HEIGHT (FT)	NEW SIGN PANELS	NEW SIGN PANELS	METAL POST	CAST IRON BASE
						(72000100) SIGN PANEL TYPE 1 (SQ. FT.)	(72000200) SIGN PANEL TYPE 2 (SQ. FT.)	(72800100) TELESCOPING STEEL SIGN SUPPORT (L.F.)	(73100100) BASE FOR TELESCOPING SIGN SUPPORT (EACH)
103+00.00	IL ROUTE 47	RT	8	7.00	2.50		17.50	29.0	2
105+79.92	IL ROUTE 47	RT	4	3.00	3.00	9.00		16.0	1
105+79.92	IL ROUTE 47	RT	9	2.00	1.00	2.00			
107+32.93	IL ROUTE 47	LT	3	2.50	3.00	7.50		15.0	1
109+54.06	IL ROUTE 47	LT	1	2.00	2.50	5.00		14.5	1
109+54.06	IL ROUTE 47	LT	3	2.00	2.50	5.00			
110+84.21	IL ROUTE 47	RT	1	2.00	2.50	5.00		14.5	1
110+84.21	IL ROUTE 47	RT	3	2.00	2.50	5.00			
113+08.45	IL ROUTE 47	RT	3	2.50	3.00	7.50		15.0	1
114+58.00	IL ROUTE 47	LT	4	3.00	3.00	9.00		16.0	1
114+58.00	IL ROUTE 47	LT	9	2.00	1.00	2.00			
118+02.06	IL ROUTE 47	LT	7	7.00	2.50		17.50	29.0	2
13+72.00	OLD OAKS RD	RT	5	2.50	2.50	6.25		14.5	1
17+72.99	WAUBONSEE DR	RT	2	2.50	3.00	7.50			
18+59.95	WAUBONSEE DR	LT	6	2.50	2.50	6.25			
	MAST ARM MOUNTED		IL RTE 47			6.75			
	MAST ARM MOUNTED		OLD OAKS RD			8.25			
	MAST ARM MOUNTED		WAUBONSEE DR				9.75		
TOTAL						92	45	164	11

20100110 TREE REMOVAL (6 TO 15 UNITS DIAMETER)			
TREE #	STATION	OFFSET	UNIT
1882	13+49.84	35.60	RT 6
1783	13+73.89	40.56	RT 9
1784	13+95.85	43.28	RT 9
1788	14+06.93	35.19	RT 7
1789	14+32.52	46.53	RT 8
1790	14+34.24	36.30	RT 11
1790A	14+34.24	36.30	RT 8
1890	14+03.30	13.34	RT 10
10	18+14.41	-22.01	LT 10
TOTAL			78

20100210 TREE REMOVAL (OVER 15 UNITS DIAMETER)			
TREE #	STATION	OFFSET	UNIT
1888	14+06.93	35.19	RT 17
TOTAL			17

IL ROUTE 47 EARTHWORK			REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	SUITABLE EARTH EXCAVATION (CUT)	SUITABLE EARTH EXCAVATION ADJUSTED FOR SHRINKAGE (25%)	EMBANKMENT (FILL)	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)
STATION	TO	STATION	PRE-STAGE CU YD	PRE-STAGE CU YD	PRE-STAGE CU YD	PRE-STAGE CU YD	PRE-STAGE CU YD
104+30.00	TO	105+00.00	4	16	12	5	7
105+00.00	TO	106+00.00	11	48	36	28	8
106+00.00	TO	107+00.00	17	61	46	26	19
107+00.00	TO	108+00.00	21	80	60	9	51
108+00.00	TO	109+00.00	36	102	76	20	57
109+00.00	TO	109+09.00	5	10	8	3	5
109+09.00	TO	109+50.00	49	53	39	195	-155
109+50.00	TO	109+85.00	41	45	34	166	-132
INTERSECTION							
110+55.00	TO	111+00.00	47	55	41	32	9
111+00.00	TO	112+00.00	64	111	84	36	48
112+00.00	TO	113+00.00	23	100	75	0	75
113+00.00	TO	114+00.00	20	95	72	0	72
114+00.00	TO	115+00.00	18	103	78	0	78
115+00.00	TO	116+00.00	16	110	83	0	83
116+00.00	TO	116+70.00	5	37	28	0	28
TOTALS =			377	1,027	770	520	250

OLD OAKS ROAD EARTHWORK			REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	SUITABLE EARTH EXCAVATION (CUT)	SUITABLE EARTH EXCAVATION ADJUSTED FOR SHRINKAGE (25%)	EMBANKMENT (FILL)	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)
STATION	TO	STATION	PRE-STAGE CU YD	PRE-STAGE CU YD	PRE-STAGE CU YD	PRE-STAGE CU YD	PRE-STAGE CU YD
11+17.65	TO	11+25.00	2	7	5	0	5
11+25.00	TO	11+50.00	7	21	16	0	16
11+50.00	TO	11+75.00	6	19	14	0	14
11+75.00	TO	12+00.00	6	19	14	0	14
12+00.00	TO	12+25.00	7	22	16	0	16
12+25.00	TO	12+50.00	8	26	20	0	20
12+50.00	TO	12+75.00	9	37	28	0	28
12+75.00	TO	13+00.00	10	53	39	0	39
13+00.00	TO	13+25.00	10	65	49	0	49
13+25.00	TO	13+50.00	10	70	53	0	53
13+50.00	TO	13+75.00	10	72	54	0	54
13+75.00	TO	14+00.00	11	70	53	2	51
14+00.00	TO	14+25.00	14	62	47	5	42
14+25.00	TO	14+50.00	13	54	41	7	34
14+50.00	TO	15+07.84	26	117	88	19	69
TOTALS =			151	715	536	33	504

WAUBONSEE DRIVE EARTHWORK			REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	SUITABLE EARTH EXCAVATION (CUT)	SUITABLE EARTH EXCAVATION ADJUSTED FOR SHRINKAGE (25%)	EMBANKMENT (FILL)	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)
STATION	TO	STATION	PRE-STAGE CU YD	PRE-STAGE CU YD	PRE-STAGE CU YD	PRE-STAGE CU YD	PRE-STAGE CU YD
16+46.03	TO	16+75.00	10	18	14	2	11
16+75.00	TO	17+00.00	8	13	10	2	8
17+00.00	TO	17+25.00	8	14	10	2	8
17+25.00	TO	17+50.00	7	11	8	2	7
17+50.00	TO	17+75.00	8	14	10	1	10
17+75.00	TO	18+00.00	10	17	13	0	13
18+00.00	TO	18+25.00	10	18	14	0	14
18+25.00	TO	18+50.00	12	22	17	0	17
18+50.00	TO	18+75.00	11	25	19	0	19
18+75.00	TO	19+00.00	12	34	25	0	25
19+00.00	TO	19+25.00	14	47	36	0	35
19+25.00	TO	19+50.00	13	46	34	1	33
19+50.00	TO	19+75.00	11	29	21	3	19
19+75.00	TO	20+00.00	9	15	11	2	9
20+00.00	TO	20+16.27	5	7	5	0	5
TOTALS =			150	330	248	16	232

EARTHWORK SUMMARY TABLE		
ITEM	UNIT	TOTAL
IL ROUTE 47 WIDENING		
EARTH EXCAVATION (20200100)	CU YD	1,027
REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL (20201200)	CU YD	377
FURNISHED EXCAVATION (20400800)	CU YD	0
OLD OAKS ROAD RECONSTRUCTION		
EARTH EXCAVATION (20200100)	CU YD	715
REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL (20201200)	CU YD	151
FURNISHED EXCAVATION (20400800)	CU YD	0
WAUBONSEE DRIVE WIDENING AND RESURFACING		
EARTH EXCAVATION (20200100)	CU YD	330
REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL (20201200)	CU YD	150
FURNISHED EXCAVATION (20400800)	CU YD	0
GRAND TOTALS		
EARTH EXCAVATION (20200100)	CU YD	2,075
REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL (20201200)	CU YD	680
FURNISHED EXCAVATION (20400800)	CU YD	0