

SPECIALTY ITEM	CODE NO	ITEM DESCRIPTION	UNIT	URBAN TOTAL QUANTITY	FEDERAL = 75%
					VILLAGE = 25%
					ROADWAY
					0005
	40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	1,520	1,520
	40600300	AGGREGATE (PRIME COAT)	TON	40	40
	40600827	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	415	415
	40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	74	74
	40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	945	945
	44000153	HOT-MIX ASPHALT SURFACE REMOVAL, 1"	SQ YD	7,400	7,400
	44201701	CLASS D PATCHES, TYPE I, 5 INCH	SQ YD	7	7
	44201705	CLASS D PATCHES, TYPE II, 5 INCH	SQ YD	99	99
	44201709	CLASS D PATCHES, TYPE III, 5 INCH	SQ YD	62	62
	44201711	CLASS D PATCHES, TYPE IV, 5 INCH	SQ YD	591	591
	48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	242	242
	67100100	MOBILIZATION	L SUM	1	1
	70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1
	70106800	CHANGEABLE MESSAGE SIGN	CAL MO	2	2
	70300100	SHORT TERM PAVEMENT MARKING	FOOT	1,000	1,000
	70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	260	260
*	78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	9,400	9,400
	X0325225	BRICK PAVEMENT REMOVAL AND REPLACEMENT	SQ FT	15	15
	Z0004510	HOT-MIX ASPHALT DRIVEWAY PAVEMENT, 3"	SQ YD	271	271

* SPECIALTY ITEM

Plotted: Apr 2, 2013 @ 1:43 PM By: Jim Schmidt - Job: 03 Sum of Quan 22/34

Engineering Enterprises, Inc.
CONSULTING ENGINEERS
52 Wheeler Road
Sugar Grove, Illinois 60054
630-466-6700 / www.eeinc.com

USER NAME =	DESIGNED -	REVISED -
	DRAWN -	REVISED -
PLOT SCALE =	CHECKED -	REVISED -
PLOT DATE =	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: N.T.S. SHEET NO. 1 OF 1 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
537	13-00004-00-RS	KANE	11	3
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT - STP			CONTRACT NO. 63850	

PRINTED BY: JIM SCHMIDT - JOB: 03 SUM OF QUAN 22/34