

SCHEDULE OF QUANTITIES

60100080 FRENCH DRAINS

CU YD LOCATION

US BUS 20				
1.25	Sta	312+50	RT	(18" Subgrade)
0.85	Sta	315+00	RT	(12" Subgrade)
1.70	Sta	317+50	RT	(24" Subgrade)
1.70	Sta	320+00	RT	(24" Subgrade)
1.25	Sta	325+00	RT	(18" Subgrade)
1.25	Sta	327+50	RT	(18" Subgrade)
1.25	Sta	330+00	RT	(18" Subgrade)
0.85	Sta	332+50	RT	(12" Subgrade)
0.85	Sta	335+00	RT	(12" Subgrade)
0.85	Sta	337+50	RT	(12" Subgrade)
0.85	Sta	340+00	RT	(12" Subgrade)
0.85	Sta	342+50	RT	(12" Subgrade)
0.85	Sta	345+00	RT	(12" Subgrade)
0.85	Sta	347+50	RT	(12" Subgrade)
0.85	Sta	350+00	RT	(12" Subgrade)
0.85	Sta	352+50	RT	(12" Subgrade)
0.85	Sta	355+00	RT	(12" Subgrade)
0.85	Sta	357+50	RT	(12" Subgrade)
0.85	Sta	360+00	RT	(12" Subgrade)
0.85	Sta	362+50	RT	(12" Subgrade)
0.85	Sta	365+00	RT	(12" Subgrade)
<u>21.15</u>	TOTAL			

60107600 PIPE UNDERDRAINS 4"

FOOT LOCATION

US BUS 20				
5,964	Sta	308+66	- 368+30	Shoulder - LT (Only if Needed)
5,964	TOTAL			

60107700 PIPE UNDERDRAINS 6"

FOOT LOCATION

US BUS 20				
4,653	Sta	313+96	- 360+49	Median Shoulder - (Under Barrier Wall)
4,653	TOTAL			

60108100 PIPE UNDERDRAINS 4" (SPECIAL)

FOOT LOCATION

US BUS 20				
18	Sta	309+42	LT - (Only if Needed)	
18	Sta	317+29	LT - (Only if Needed)	
18	Sta	318+78	LT - (Only if Needed)	
18	Sta	326+28	LT - (Only if Needed)	
18	Sta	330+26	LT - (Only if Needed)	
18	Sta	334+27	LT - (Only if Needed)	
18	Sta	338+27	LT - (Only if Needed)	
18	Sta	342+27	LT - (Only if Needed)	
18	Sta	346+29	LT - (Only if Needed)	
18	Sta	350+77	LT - (Only if Needed)	
18	Sta	355+30	LT - (Only if Needed)	
18	Sta	357+62	LT - (Only if Needed)	
18	Sta	359+27	LT - (Only if Needed)	
18	Sta	363+28	LT - (Only if Needed)	
<u>252</u>	TOTAL			

60221000 MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, OPEN LID

EACH LOCATION

US BUS 20				
1	Sta	315+27	LT	
1	TOTAL			

60270050 DRAINAGE STRUCTURES, TYPE 4 WITH TWO TYPE 20 FRAMES AND GRATES

EACH LOCATION

US BUS 20		
1	Sta	316+40
1	Sta	318+00
1	Sta	318+60
1	Sta	319+50
1	Sta	325+50
1	Sta	328+00
1	Sta	330+50
1	Sta	333+00
1	Sta	335+00
1	Sta	337+70
1	Sta	340+20
1	Sta	342+70
1	Sta	345+50
1	Sta	348+50
1	Sta	352+50
1	Sta	356+00
1	Sta	357+00
1	Sta	358+00
<u>18</u>	TOTAL	

60270055 DRAINAGE STRUCTURES, TYPE 5 WITH TWO TYPE 22 FRAMES AND GRATES

EACH LOCATION

US BUS 20		
1	Sta	317+30
1	Sta	357+44
<u>2</u>	TOTAL	