

SCHEDULE OF QUANTITIES

HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50						40603310
			WIDTH	SQYD	INCHES	TONS
Stage I EB	4159+50.00	4167+00.00	4	333.3	2	37.3
Stage II EB	4159+50.00	4161+00.00	4	66.7	2.0	7.5
Stage III WB	4165+50.00	4167+50.00	4	88.9	2	10.0
Stage IV WB	4160+00.00	4167+00.00	4	311.1	2	34.8
TOTAL						89.6

HOT-MIX ASPHALT SURFACE REMOVAL, 2"					44000157
			WIDTH	SQYD	
Stage I EB	4159+50.00	4167+00.00	4	333.3	
Stage II EB	4159+50.00	4161+00.00	4	66.7	
Stage III WB	4165+50.00	4167+50.00	4	88.9	
Stage IV WB	4160+00.00	4167+00.00	4	311.1	
TOTAL					800

SHOULDER RUMBLE STRIPS, 16 INCH					64200116
					FOOT
EB Median	4159+50.00	4167+00.00			750
EB Outside	4159+50.00	4161+00.00			150
WB Outside	4165+50.00	4167+50.00			200
WB Median	4160+00.00	4167+00.00			700
TOTAL					1,800

SHORT TERM PAVEMENT MARKING						70300100
STAGE I						FOOT
EASTBOUND						
6" SKIP DASH	4144+50.00	4154+50.00	500			250
4" WHITE	4159+50.00	4167+00.00	750			250
6" SKIP DASH	4167+50.00	4170+00.00	125			63
STAGE II						
EASTBOUND						
4" WHITE	4159+50.00	4164+00.00	450			150
6" SKIP DASH	4164+00.00	4167+00.00	150			75
STAGE III						
WESTBOUND						
6" SKIP DASH	4172+50.00	4182+50.00	500			250
4" WHITE	4163+00.00	4167+50.00	450			150
6" SKIP DASH	4159+50.00	4163+00.00	175			88
STAGE IV						
WESTBOUND						
4" WHITE	4160+00.00	4167+00.00	700			234
6" SKIP DASH	4158+50.00	4161+00.00	50			25
TOTAL						1,535
USE						1,560

WORK ZONE PAVEMENT MARKING REMOVAL						70301000
PAVEMENT MARKING TAPE, TYPE III 4"						70300520
STAGE I						
EASTBOUND						SQ FT
	4144+50.00	4170+00.00				850
	4159+50.00	4167+00.00	750			250
(8" GORE PM)	4168+85.00	4172+00.00				210
(8" GORE PM)	4168+85.00	4170+15.00				87
(8" CHEVRONS)	4168+85.00	4170+15.00				40
STAGE II						
EASTBOUND						
	4144+50.00	4167+00.00	2250			750
(25' SKIP DASH)	4159+50.00	4164+00.00				150
	4164+00.00	4167+00.00				50
STAGE III						
WESTBOUND						
	4159+00.00	4182+50.00	2350			784
	4163+00.00	4167+50.00				150
(25' SKIP DASH)	4159+75.00	4163+00.00				54
STAGE IV						
WESTBOUND						
(8" GORE PM)	4157+00.00	4159+00.00				400
(8" GORE PM)	4157+50.00	4159+00.00				300
(8" CHEVRONS)	4158+00.00	4159+00.00				120
	4158+00.00	4182+00.00				2,400
	4160+00.00	4167+00.00	700			234
TOTAL						14,043
USE						14,100

TEMPORARY CONCRETE BARRIER					70400100
STAGE I					FOOT
4159+83.40	4165+05.74	EB			512.5
TOTAL					512.5

RELOCATE TEMPORARY CONCRETE BARRIER					70400200
STAGE II					FOOT
4160+98.31	4165+05.97	EB			400
4161+98.28	4166+00.73	WB			400
4161+98.05	4166+89.00	WB			487.5
TOTAL					1287.5

IMPACT ATTENUATORS, TEMPORARY (NON- REDIRECTIVE), TEST LEVEL 3					Z0030250
STAGE I					
4159+83.40	EB				1
TOTAL					1

IMPACT ATTENUATORS, RELOCATE (NON- REDIRECTIVE), TEST LEVEL 3					Z0030350
STAGE II					EACH
4160+98.31	EB				1
4166+00.73	WB				1
4166+89.00	WB				1
TOTAL					3

PAVEMENT MARKING REMOVAL						78300100
STAGE I						
EASTBOUND						FOOT
6" SKIP DASH	4144+50.00	4154+50.00	500			250
4" WHITE	4159+50.00	4167+00.00	750			250
6" SKIP DASH	4166+00.00	4170+00.00	275			138
STAGE II						
EASTBOUND						
4" WHITE	4159+50.00	4164+00.00	450			150
6" SKIP DASH	4164+00.00	4167+00.00	150			75
STAGE III						
WESTBOUND						
6" SKIP DASH	4172+50.00	4182+50.00	500			250
4" WHITE	4163+00.00	4167+50.00	450			150
6" SKIP DASH	4159+50.00	4163+00.00	175			88
STAGE IV						
WESTBOUND						
4" WHITE	4160+00.00	4167+00.00	700			234
6" SKIP DASH	4158+50.00	4161+00.00	50			25
TOTAL						1,660
USE						1,700

POLYUREA PAVEMENT MARKING TYPE I - LINE 4"					78008210
STAGE I					FOOT
EASTBOUND	4159+50.00	4167+00.00			750
STAGE II					
EASTBOUND	4159+50.00	4164+00.00			450
STAGE III					
WESTBOUND	4163+00.00	4167+50.00			450
STAGE IV					
WESTBOUND	4160+00.00	4167+00.00			700
TOTAL					2,350

POLYUREA PAVEMENT MARKING TYPE I - LINE 6"					78008230
STAGE I					FOOT
EASTBOUND	4144+50.00	4154+50.00	500		
EASTBOUND	4166+00.00	4170+00.00	275		
STAGE II					
EASTBOUND	4164+00.00	4167+00.00	150		
STAGE III					
WESTBOUND	4172+50.00	4182+50.00	500		
WESTBOUND	4159+50.00	4163+00.00	175		
STAGE IV					
WESTBOUND	4158+50.00	4161+00.00	50		
TOTAL					1,750

REPLACEMENT REFLECTOR					78100300
EASTBOUND					EACH
SKIP-DASH	4144+50.00	4154+50.00			22
WESTBOUND					
SKIP-DASH	4172+50.00	4182+50.00			22
TOTAL					44

DATE	
BY	
REVISION	
NO.	
DESCRIPTION	

DATE	
BY	
REVISION	
NO.	
DESCRIPTION	

FILE NAME: 0204127-shr-estwdule.dgn
 PLOT DATE: 07/29/2012
 PLOT SCALE: 1/8"=1'-0"



DESIGNED - G.P.L./K.R.K. REVISION -
 DRAWN - K.R.K. REVISION -
 CHECKED - S.M.M. REVISION -
 DATE - JULY 2012 REVISION -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES
I-39 OVER I-88

SCALE: NONE SHEET NO. 1 OF 1 SHEETS STA. TO STA.

F.A.I. R.T.E.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
39	02 BRIDGE PAINTING 2013-2	OSLE	26	5
CONTRACT NO. 64J2T				
ILLINOIS FED. AID PROJECT				