

DATE	
BY	
DESIGNED	
DRAWN	
CHECKED	
DATE	
NO.	

DATE	
BY	
DESIGNED	
DRAWN	
CHECKED	
DATE	
NO.	

SUMMARY OF QUANTITIES				CONSTRUCTION CODE		
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	0014 BRIDGE REPAIR 100% STATE		
20200500	EARTH EXCAVATION (WIDENING)	CU YD	524	524		
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	461	461		
25100630	EROSION CONTROL BLANKET	SQ YD	461	461		
28000400	PERIMETER EROSION BARRIER	FOOT	1056	1056		
31100910	SUBBASE GRANULAR MATERIAL, TYPE A 12"	SQ YD	945	945		
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	44	44		
40603080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	45	45		
40603310	HOT-MIX ASPHALT SURFACE COURSE, MX "C", N50	TON	145	145		
44000156	HOT-MIX ASPHALT SURFACE REMOVAL, 1 3/4"	SQ YD	501	501		
44000161	HOT-MIX ASPHALT SURFACE REMOVAL, 3"	SQ YD	174	174		
48203022	HOT-MIX ASPHALT SHOULDERS, 6 1/4"	SQ YD	830	830		
50102400	CONCRETE REMOVAL	CU YD	4.0	4.0		
50104000	BRIDGE RAIL REMOVAL	FOOT	134	134		
50300225	CONCRETE STRUCTURES	CU YD	4.7	4.7		

\* SPECIALTY ITEM

FILE NAME \*0264421\*shl-50081.dgn  
 PLOT DATE \*3/8/2013  
 PLOT SCALE \*100.0000 \* / IN.



CHRISTIAN-ROGE & ASSOCIATES, INC.  
 ENGINEERS-PLANNERS-SURVEYORS  
 211 WEST WACKER DRIVE  
 CHICAGO, ILLINOIS 60606  
 PHONE: (312)372-2023 FAX: (312)372-6274

DESIGNED - M.P.  
 DRAWN - K.R.K.  
 CHECKED - M.P./K.R.K.  
 DATE - JANUARY 2013

REVISED -  
 REVISED -  
 REVISED -  
 REVISED -

STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES  
 I-78 OVER EAST FORK PLUM RIVER

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
642	D2 DECK REPAIR 2013-4	CARROLL	25	3
CONTRACT NO. 64J55			ILLINOIS	