163

M002 M001 M002 M002 M001 M001

•LOCAL FUNDING FORMULA

1. 80% STU FUNDS TO BE USED FOR LOCAL SHARE PROJECT NTE $1,060,000 FROM CMAP.
2. 80% STP-BR FUNDS TO BE USED SECOND FOR LOCAL SHARE OF PROJECT.
3. 20% OF LOCAL SHARE TO BE DIVIDED EQUALLY BETWEEN VILLAGE OF MINOOKA AND GRUNDY COUNTY. ••ONLY GRUNDY COUNTY WILL BE BILLED.

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE: 90% FEDERAL 10% STATE ROADWAY 0003	80% FEDERAL• 20% COUNTY ROADWAY 0003	90% FEDERAL 10% STATE BRIDGE 0010 SN 032-0119	90% FEDERAL 10% STATE BOX CULVERT 0040	80% FEDERAL• 20% COUNTY BRIDGE 0010 SN 032-0119	80% FEDERAL• 20% COUNTY BOX CULVERT 0040
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	907	907					
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	436	436					
20200100	EARTH EXCAVATION	CU YD	25379	25379					
△1 20101000	TEMPORARY FENCE	FOOT	692	692					
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	319				319		
20400800	FURNISHED EXCAVATION	CU YD	46445	29750	16695				
20700220	POROUS GRANULAR EMBANKMENT	CU YD	517			208	292	17	
20800150	TRENCH BACKFILL	CU YD	34	34					
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	32183	32183					
25000100	SEEDING, CLASS 1	ACRE	0.65	0.65					
25000200	SEEDING, CLASS 2	ACRE	7.1	7.1					
25000300	SEEDING, CLASS 3	ACRE	3.43	3.43					
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	1006	1006					
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	1006	1006					
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	1006	1006					

14

△SPECIALTY ITEMS

△1 Rev. 6-4-13

FILE NAME = c:\pw_work\pwidot\duncanbd\dms58037\apd1904-sht-500.dgn	USER NAME = duncanbd	DESIGNED -	REVISED -
	PLOT SCALE = 100.0000 ' / in.	DRAWN -	REVISED -
	PLOT DATE = 3/15/2013	CHECKED -	REVISED -
		DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: | SHEET NO. 1 OF 12 SHEETS | STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
80	(32,47-4)HBR-2	GRUNDY	143	3
		CONTRACT NO. 66873		
	ILLINOIS FED. AID PROJECT			