

- LOCAL FUNDING FORMULA
 1. 80% STU FUNDS TO BE USED FOR LOCAL SHARE PROJECT NTE \$1,060,000 FROM CMAP.
 2. 80% STP-BR FUNDS TO BE USED SECOND FOR LOCAL SHARE OF PROJECT.
 3. 20% OF LOCAL SHARE TO BE DIVIDED EQUALLY BETWEEN VILLAGE OF MINOOKA AND GRUNDY COUNTY. **ONLY GRUNDY COUNTY WILL BE BILLED

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE					
				90% FEDERAL 10% STATE ROADWAY 0003	80% FEDERAL • 20% COUNTY ROADWAY 0003	90% FEDERAL 10% STATE BRIDGE 0010 SN 032-0119	90% FEDERAL 10% STATE BOX CULVERT 0040	80% FEDERAL • 20% COUNTY BRIDGE 0010 SN 032-0119	80% FEDERAL • 20% COUNTY BOX CULVERT 0040
				50500505	STUD SHEAR CONNECTORS	EACH	7452		
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	343010			262870	820	79320	
50800515	BAR SPLICERS	EACH	196			138		58	
50901720	BICYCLE RAILING	FOOT	683	238		445			
50901750	PARAPET RAILING	FOOT	437			437			
51100100	SLOPE WALL 4 INCH	50 YD	947			690		257	
51201400	FURNISHING STEEL PILES HP10X42	FOOT	2863			2067		796	
51202305	DRIVING PILES	FOOT	2863			2067		796	
51203400	TEST PILE STEEL HP10X42	EACH	3			3			
51500100	NAME PLATES	EACH	2			1	1		
52000110	PREFORMED JOINT STRIP SEAL	FOOT	197			140		57	
52100020	ELASTOMERIC BEARING ASSEMBLY, TYPE II	EACH	18			12		6	
52100540	ANCHOR BOLTS, 1 1/2"	EACH	54			36		18	
54003000	CONCRETE BOX CULVERTS	CU YD	13.9				13.9		

14
 ΔSPECIALTY ITEMS

FILE NAME : c:\pwork\pwork\duncenbd\dm50827\ep8	USER NAME : duncenbd 904-shi-500.dgn	DESIGNED - DRAWN - CHECKED - DATE -	REVISED - REVISED - REVISED - REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES		F.A.I. RTE: 80	SECTION (32,47-4)HBR-2	COUNTY GRUNDY	TOTAL SHEETS 143	SHEET NO. 7
PLOT SCALE : 100.0000' / in. PLOT DATE : 3/15/2013					SCALE:	SHEET 5 OF 12 SHEETS	STA. TO STA.	ILLINOIS FED. AID PROJECT		CONTRACT NO. 66873	