

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTR. CODE	
				100% CONTRACT MAINT.	
				LASALLE CO.	KENDALL CO.
				ROADWAY 0014 RURAL	ROADWAY 0014 RURAL
21101505	TOPSOIL EXCAVATION AND PLACEMENT	CU YD	64	20	44
25000210	SEEDING, CLASS 2A	ACRE	0.12	0.04	0.08
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	12	4	8
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	12	4	8
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	12	4	8
25100630	EROSION CONTROL BLANKET	SQ YD	1008	332	676
25100635	HEAVY DUTY EROSION CONTROL BLANKET	SQ YD	1625	540	1085
28000400	PERIMETER EROSION BARRIER	FOOT	1200	400	800
48101200	AGGREGATE SHOULDERS, TYPE B	TON	40	8	32
50102400	CONCRETE REMOVAL	CU YD	57	22	35
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	5980	2180	3800
54003000	CONCRETE BOX CULVERTS	CU YD	57	22	35
63000350	LONG-SPAN GUARDRAIL OVER CULVERT, 12 FT 6 IN SPAN	FOOT	152	76	76
63200310	GUARDRAIL REMOVAL	FOOT	152	76	76
63301210	REMOVE AND REERECT STEEL PLATE BEAM GUARDRAIL, TYPE A	FOOT	156	156	
63301990	REMOVE AND REERECT TRAFFIC BARRIER TERMINALS, TYPE 1	EACH	2	2	
67100100	MOBILIZATION	L SUM	1	0.5	0.5
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	0.33	0.67
70400100	TEMPORARY CONCRETE BARRIER	FOOT	276	276	
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	1104		1104
70600251	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE, NARROW), TEST LEVEL 3	EACH	4	4	
70600352	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE, NARROW), TEST LEVEL 3	EACH	16		16
78200410	GUARDRAIL MARKERS, TYPE A	EACH	22	14	8
X0322121	SHEET WATERPROOFING MEMBRANE SYSTEM	SQ YD	95	32	63
X2020502	BRACED EXCAVATION	CU YD	528	176	352
Z0012754	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SQ FT	19	9	10
Z0015500	DEBRIS REMOVAL	L SUM	1	0.5	0.5

Rev.