

GUARD RAIL SCHEDULE							
STA. - STA.	LT	RT	GUARDRAIL REMOVAL	LONG-SPAN GUARDRAIL OVER CULVERT	REMOVE & RE- ERECT STEEL PLATE BEAM GUARDRAIL, TYPE A	REMOVE & RE- ERECT TRAFFIC BARRIER TERMINAL, TYPE 1	GUARDRAIL MARKERS, TYPE A
LASALLE COUNTY			FOOT	FOOT	FOOT	FOOT	EACH
LOCATION 2							
459+95 - 463+52		X					9
462+05 - 464+05	X						5
462+05 - 462+22	X				17		
462+21 - 462+59	X		38	38			
462+21 - 462+59		X	38	38			
462+59 - 463+02		X			43		
462+59 - 463+55	X				96		
463+02 - 463+52		X				1	
463+55 - 464+05	X					1	
TOTALS			76	76	156	2	14

EARTHWORK SCHEDULE										
STA. - STA.	LT	RT	TOPSOIL EXCAVATION & PLACEMENT	BRACED EXCAVATION	SEEDING, CLASS 2A	NITROGEN FERTILIZER NUTRIENT	PHOSPHORUS FERTILIZER NUTRIENT	POTASSIUM FERTILIZER NUTRIENT	PERIMETER EROSION BARRIER	HEAVY DUTY EROSION CONTROL BLANKET
LASALLE COUNTY			CU YD	CU YD	ACRE	POUND	POUND	POUND	FOOT	SQ YD
LOCATION 1										
342+93 - 343+63	X		5	40	0.01	0.9	0.9	0.9	100	82
342+93 - 343+63		X	5	40	0.01	0.9	0.9	0.9	100	82
LOCATION 2										
462+05 - 462+75	X		5	48	0.01	0.9	0.9	0.9	100	84
462+05 - 462+75		X	5	48	0.01	0.9	0.9	0.9	100	84
TOTALS			20	176	0.4	3.6	3.6	3.6	400	332

BARRIER WALL SCHEDULE						
STA.-STA.	LT	RT	TEMPORARY CONCRETE BARRIER	RELOCATE TEMPORARY CONCRETE BARRIER	IMPACT ATTENUATORS	RELOCATE IMPACT ATTENUATORS
LASALLE COUNTY			FOOT	FOOT	EACH	EACH
LOCATION 2						
461+58 - 463+22	X		138		2	
461+58 - 463+22		X	138		2	
TOTALS			276		4	