

CODE NO.	ITEM	UNIT	CONSTR. CODE
			STATE FUNDS 100% STATE STRUCTURE 0014 RURAL
50102400	CONCRETE REMOVAL	CU YD	7.6
50300225	CONCRETE STRUCTURES	CU YD	7.6
50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	266
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	1516
50800530	MECHANICAL SPLICERS	EACH	40
52100520	ANCHOR BOLTS, 1"	EACH	16
67100100	MOBILIZATION	L SUM	1
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1
70400100	TEMPORARY CONCRETE BARRIER	FOOT	1070
70600280	IMPACT ATTENUATORS, TEMPORARY (SEVERE USE,NARROW), TEST LEVEL 3	EACH	6
X5210025	ELASTOMERIC BEARING ASSEMBLY, TYPE II (SPECIAL)	EACH	4
X7010216	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1
X7010600	TRAFFIC CONTROL AND PROTECTION, STANDARD 701406, SPECIAL	L SUM	1
Z0001899	JACK AND REMOVE EXISTING BEARINGS	EACH	4
Z0012754	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SQ FT	17
Z0073200	TEMPORARY SHORING AND CRIBBING	EACH	8

No

Rev.

FILE NAME =	USER NAME = peteluj	DESIGNED - YOGESH PATEL	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.I. RTE. 80	SECTION 03 PIER CAP REPAIR 2014-1	COUNTY LASALLE	TOTAL SHEETS 25	SHEET NO. 3	
of\pwr\pwidot\peteluj\08320332\0366	71-shr-details.dgn	DRAWN - YOGESH PATEL	REVISED -			SCALE:	SHEET NO. 1 OF 1 SHEETS	STA.	TO STA.	ILLINOIS	CONTRACT NO. 66C71
	PLOT SCALE = 99.9999 1/1 in.	CHECKED - RON WOODSHANK	REVISED -								
	PLOT DATE = 4/3/2013	DATE -	REVISED -								