

SCHEDULE
PAVEMENT MARKING
NORTHBOUND LANES

LOCATION MILE POST	MODIFIED URETHANE PAVEMENT MARKING LINE 4"		MODIFIED URETHANE PAVEMENT MARKING LINE 6"
	FEET		FEET
	YELLOW	WHITE	WHITE
266.80	6	6	10
268.32	6	6	10
268.34		6	10
268.53	6	6	10
268.84	6	6	10
269.25	6	6	10
269.44	6	6	10
271.00	6	6	10
271.10	6	6	10
271.42		6	10
272.18		6	10
272.95		6	10
273.74		6	10
277.02		6	10
277.10		6	10
277.39	6	6	10
277.52	6	6	10
277.58		6	10
278.02		6	10
278.30	6		10
278.45		6	10
278.66		6	10
280.82		6	10
281.32		6	10
282.00		6	10
283.10		6	10
283.42		6	10
284.04		6	10
284.40		6	10
284.50		6	10
284.90	6	6	10
285.00	6	6	10
285.52	6	6	10
286.50	6	6	10
287.59		6	10
287.68		6	10
288.80	6	6	10
289.10	6		10
289.62	6	6	10
PAGE 1 TOTAL	108	222	390

SCHEDULE
PAVEMENT MARKING
NORTHBOUND LANES

LOCATION MILE POST	MODIFIED URETHANE PAVEMENT MARKING LINE 4"		MODIFIED URETHANE PAVEMENT MARKING LINE 6"
	FEET		FEET
	YELLOW	WHITE	WHITE
292.34		6	10
292.50		6	10
292.60		6	10
293.08		6	10
293.15	6		10
293.82	6		10
294.04	6		10
299.70	6	6	10
300.52	6	6	10
300.58	6	6	10
PAGE 2 TOTAL	36	42	100
NB TOTALS	408		490

SCHEDULE
PAVEMENT MARKING
NORTHBOUND RAMPS

LOCATION EXIT NO.	L.M.	MODIFIED URETHANE PAVEMENT MARKING LINE 4"		
		FEET		
		YELLOW	WHITE	
272	EXIT	0.02	6	6
		0.07	6	6
		0.14	6	6
		0.23	6	6
		0.01	6	6
	ENTRANCE	0.06	6	6
		0.11	6	6
		0.15	6	6
		0.21	6	6
		0.02	6	6
280	EXIT	0.18	6	6
		0.20	6	6
	ENTRANCE	0.04	6	6
		0.12	6	6
		0.19	6	6
		0.23	6	6
283	EXIT	0.05	6	6
		0.18	6	6
	ENTRANCE	0.20	6	6
		0.03	6	6
		0.08	6	6
		0.12	6	6
		0.19	6	6
		0.2	6	6
PAGE TOTAL		144	144	
NB RAMP TOTALS		288		