

CLASS A PATCHING SCHEDULE SOUTHBOUND LANES

LOCATION BY MILE POST	DRIVING LANE				PASSING LANE			
	TYPE II 12"	PATCH REINF.	PAV'T FABRIC	SAW CUTS	TYPE II 12"	PATCH REINF.	PAV'T FABRIC	SAW CUTS
	SQ YD	SQ YD	SQ YD	FOOT	SQ YD	SQ YD	SQ YD	FOOT
264.48	8	8	8	60	8	8	8	60
264.46	8	8	8	60	8	8	8	60
264.45	8	8	8	60	8	8	8	60
264.40	8	8	8	60	8	8	8	60
264.31	8	8	8	60				
264.29	8	8	8	60	8	8	8	60
264.27	8	8	8	60	8	8	8	60
264.26	8	8	8	60				
264.22	8	8	8	60	8	8	8	60
264.21	8	8	8	60	8	8	8	60
264.20	8	8	8	60				
264.18	8	8	8	60				
264.16	8	8	8	60				
264.11	8	8	8	60				
264.00	8	8	8	60				
263.96					8	8	8	60
263.86					8	8	8	60
263.84					8	8	8	60
263.38	8	8	8	60	8	8	8	60
263.37	8	8	8	60	8	8	8	60
263.34	8	8	8	60	8	8	8	60
263.30	8	8	8	60				
263.29	8	8	8	60				
263.19	8	8	8	60				
263.10					8	8	8	60
263.04					8	8	8	60
263.02					8	8	8	60
262.80					11	11	11	64
262.77	8	8	8	60				
262.76	8	8	8	60				
262.68	8	8	8	60				
262.52	8	8	8	60				
262.19	13	13	13	68	13	13	13	68
259.22	8	8	8	60	8	8	8	60
258.40	8	8	8	60				
258.30					11	11	11	64
TOTALS	229	229	229	1688	179	179	179	1276

CLASS B PATCHING SCHEDULE SOUTHBOUND LANES

LOCATION BY L.M.	RAMPS			
	TYPE II 12"	DOWEL BARS	SAW CUTS	PAVE'T FABRIC
	SQ YD	EACH	FOOT	SQ YD
EXIT RAMP #216				
0.02	11	28	60	11
0.06	11	28	60	11
0.14	11	28	60	11
2.00	11	28	60	11
ENTRANCE RAMP #216				
0.04	11	28	60	11
0.18	11	28	60	11
0.23	11	28	60	11
TOTALS	77	196	420	77

•ALL EXIT RAMPS: L.M. = 0.00 = BEGINNING OF GORE AREA

••ALL ENTRANCE RAMPS: L.M. = 0.00 = TOP OF RAMP CONST. JT.