GUARDRAIL SCHEDULE

STATION FROM	STATION TO		STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS (FOOT)	TRAFFIC BARRIER TERMINAL, TYPE 6 (EACH)	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT (EACH)	GUARDRAIL REMOVAL (FOOT)	TEMPORARY STEEL PLATE BEAM GUARDRAIL, TYPE A (FOOT)	TEMPORARY TRAFFIC BARRIER TERMINAL, TYPE 5 (EACH)	TEMPORARY TRAFFIC BARRIER TERMINAL, TYPE 6 (EACH)	TEMPORARY TRAFFIC BARRIER TERMINAL, TYPE 1, SPECIAL (TANGENT) (EACH)
314+87.28	316+12.28	SB OUTSIDE					125.0			
316+12.28	316+26.95	SB OUTSIDE						1		
314+04.82	314+54.82	NB CROSSOVER								1
314+54.82	316+17.32	NB CROSSOVER					162.5			
316+17.32	316+61.07	NB CROSSOVER							1	
318+00.68	318+43.83	SB OUTSIDE		1						
318+43.83	320+38.73	SB OUTSIDE	175.0							
320+38.73	320+88.30	SB OUTSIDE			1					
318+01.00	319+22.00	SB OUTSIDE				101				
318+34.00	319+67.00	SB INSIDE				113				
314+13.32	314+63.32	NB INSIDE			1					
314+63.32	316+25.82	NB INSIDE	162.5							
314+97.77	315+47.77	NB OUTSIDE			1					
315+47.77	316+47.77	NB OUTSIDE	100.0							
316+25.22	316+68.37	NB INSIDE		1						
316+47.17	316+90.32	NB OUTSIDE		1						
318+34.20	318+77.35	SB INSIDE		1						
318+77.95	321+21.66	SB INSIDE	225.0							
321+21.66	321+71.53	SB INSIDE			1					
315+85.09	316+93.66	NB INSIDE				107				
316+24.00	317+23.00	NB OUTSIDE				100				
TOTAL			662.5	4	4	421	287.5	1	1	1

NOTE:
ALL STATIONS AND OFFSETS ARE BASED ON MEDIAN SURVEYLINE UNLESS OTHERWISE NOTED.

TERRA ENGINEERING LTD.

USER NAME = WAH	DESIGNED - CL	REVISED -
	DRAWN - WAH	REVISED -
PLOT SCALE = 2.0000 ' / in.	CHECKED - KJC/HTL	REVISED -
PLOT DATE = 12/13/2012	DATE - 10/04/12	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULES OF QUANTITIES
IL 116 OVER TEN MILE CREEK

SCALE: NTS | SHEET NO. 4 OF 7 SHEETS | STA. | TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
673	(102B-1)BR	TAZEWELL	89	15

CONTRACT NO. 68671
ILLINOIS FED. AID PROJECT

I:\Terra Bentley\V8i\Standards\ILDOT\IdotStd\tables\pen\PLOTLABEL.TBL
ILDOT_PDFNOLAYERS_BW.pltcfg
T:\Projects\10-221_IDOT-TazBridges_Ten Mile Creek-Phase II\Drawings\CADD Sheets\0468671-sht-Schedules-4.dgn