

EROSION CONTROL SCHEDULE					
	EROSION CONTROL BLANKET	TEMPORARY EROSION CONTROL SEEDING	TEMPORARY DITCH CHECKS	PERIMETER EROSION CONTROL BARRIER	INLET AND PIPE PROTECTION
	SQ. YD	(POUND)	(FOOT)	(FOOT)	(EACH)
STA. 309+00 TO STA. 317+00 MEDIAN		22			
STA. 319+00 TO STA. 325+00 MEDIAN		34			
STA. 313+00 - STA. 316+57 W. FORESLOPE	1422				
STA. 313+00 - STA. 317+00 NB RT		25			
STA. 319+00 TO STA. 325+00 NB RT		19			
STA. 314+62.71 MEDIAN			16.00		
STA. 316.53.30 MEDIAN			16.00		
STA. 319+20.10 MEDIAN					1
STA. 320+86.42 MEDIAN			16.00		
STA. 322+85.62 MEDIAN					1
STA. 316+60 TO STA. 317+00 MEDIAN				44	
STA. 313+00 TO STA. 320+00 NB RT				584	
STA. 318+30 TO STA. 318+70 MEDIAN				41	
STA. 319+00 TO STA. 320+22 SB LT				406	
STA. 316+00 TO STA. 319+25 (UNDERNEATH THE BRIDGE)					
TOTALS	1422	100	48	1075	2

MOWING				
LOCATION	LENGTH	WIDTH	No. MOWINGS / CONSTRUCTION DURATION	AREA
	FOOT	FOOT		ACRE
STA. 308+00.00 to STA. 325+00.00	1517	15	2	0.52
		30	2	1.04
		15	2	0.52
TOTALS				4.25

TEMPORARY LIGHTING SCHEDULE	
LOCATION	TEMPORARY LIGHTING SYSTEM
	(EACH)
PROJECT WIDE	1
TOTALS	1

TEMP SIGN ASSEMBLY			
LOCATION	HEIGHT	WIDTH	AREA
	FOOT	FOOT	SQ. FT
EASTBOUND IL 116 BTWN US 24 & IL 26 EXACT LOCATION TO BE DETERMINED BY THE ENGINEER	6	11	66
TOTAL			66

TEMPORARY CONCRETE BARRIER SCHEDULE	
LOCATION	TEMPORARY CONCRETE BARRIER (FOOT)
RT. STA. 311+25.00 TO LT. STA. 323+19.24	1,178
TOTAL	1,178

TRAFFIC CONTROL SCHEDULE				
	TRAFFIC CONTROL AND PROTECTION STANDARD	TRAFFIC CONTROL AND PROTECTION STANDARD	TRAFFIC CONTROL SURVEILLANCE	CHANGEABLE MESSAGE SIGN
	701422 (L SUM)	701416 (EACH)	(CAL DA)	(CAL MO)
PROJECT WIDE	1	1	26	2
TOTALS	1	1	26	2

MOBILIZATION SCHEDULE	
LOCATION	MOBILIZATION (L SUM)
PROJECT WIDE	1
TOTALS	1

ENGINEERS FIELD OFFICE SCHEDULE	
	ENGINEER'S FIELD OFFICE, TYPE A
	(CAL MO)
PROJECT WIDE	9
TOTALS	9

MODULAR BLADE - TYPE GLARE SCREENS	
LOCATION	CONSTRUCTION
	FOOT
313+50 LT TO 322+00 LT	850
TOTALS	850

CONSTRUCTION LAYOUT SCHEDULE	
LOCATION	CONSTRUCTION
	(EACH)
PROJECT WIDE	1
TOTALS	1

WINGWALL MODIFICATION SN 090-0110		
ITEM	UNITS	QUANTITY
CONCRETE REMOVAL	CU YD	0.8
CONCRETE STRUCTURES	CU YD	1.60
REINFORCEMENT BARS, EPOXY COATED	POUND	160

NOTE:
ALL STATIONS AND OFFSETS ARE BASED ON MEDIAN SURVEYLINE UNLESS OTHERWISE NOTED.