CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODES: 80% FED. 20% STATE — ROADWAY 0004 RURAL	BRIDGE 0011 SN 090-0178	100% STATE — MOWING 0004
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	950	950		
28000305	TEMPORARY DITCH CHECKS	FOOT	90	90		
28000400	PERIMETER EROSION BARRIER	FOOT	2999	2999		
28100107	STONE RIPRAP, CLASS A4	SQ YD	3255		3255	
28200200	FILTER FABRIC	SQ YD	3255		3255	
31101000	SUBBASE GRANULAR MATERIAL, TYPE B	TON	795	795		
40600215	POLYMERIZED BITUMINOUS MATERIALS (PRIME COAT)	TON	3	3		
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	348	348		
40600990	TEMPORARY RAMP	SQ YD	457	457		
40603080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	984	984		
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	255	255		
42001430	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)	SQ YD	57	57		
44000100	PAVEMENT REMOVAL	SQ YD	420	420		
48101200	AGGREGATE SHOULDERS, TYPE B	TON	178	178		

* SPECIALTY ITEM

TERRA ENGINEERING LTD.

USER NAME = M1 | PLOT SCALE = N/A | PLOT DATE = 3/19/2013

DESIGNED - CL | DRAWN - KJC | CHECKED - LVA | DATE - 03/20/13

REVISED - | REVISED - | REVISED - | REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES
IL 9 OVER MUD CREEK

SCALE: N/A | SHEET NO. 2 OF 7 SHEETS | STA. | TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
693	(119BR) BR	TAZEWELL	80	5

CONTRACT NO. 68757

ILLINOIS FED. AID PROJECT