

LOCATION	CURB & GUTTER REMOVAL	SIDEWALK REMOVAL SPECIAL	SIDEWALK REMOVAL	PCC SIDEWALK SPECIAL	PCC SIDEWALK 4"	COMB. CURB & GUTTER, TYP B-6.12	DETECTABLE WARNINGS	POROUS GRANULAR EMBANKMENT SPECIAL
	80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE
	FT	SQ FT	SQ FT	SQ FT	SQ FT	FT	SQ FT	CU YD
<b>NE QUADRANT:</b>								
GRANT STREET			19.5		85.0		10.0	
WILLOW STREET		149.5		149.5			25.0	
CHESTNUT STREET			34.5		34.5		10.0	
CEDAR STREET		188.0	38.0	188	47.5		50.3	
MAIN STREET		406.0		406			40.5	
TOPEKA STREET		208.0		208			20.0	
ATCHISON STREET		104.7		104.7			37.7	
<b>NW QUADRANT:</b>								
LINCOLN STREET			58.5		85.0		10.0	
WILLOW STREET		318.5			347.8		20.0	
CHESTNUT STREET		180.3		192.3			77.5	
CEDAR STREET			114.0		181.5		20.0	
MAIN STREET		293.5		293.5			31.8	
TOPEKA STREET		167.2		167.2			20.0	
ATCHISON STREET			116.8		141.0		20.0	
1ST STREET			84.4		105.5		10.0	
2ND STREET			65.2		81.5		10.0	
3RD STREET			50.0		62.5		10.0	
<b>SE QUADRANT:</b>								
GRANT STREET			93.6		212.5		20.0	
LINCOLN STREET			46.8		60.0		10.0	
WILLOW STREET			95.6		122.5		20.0	
CHESTNUT STREET			114.0		203.8		10.0	
CEDAR STREET		350.0		372.5			48.3	
MAIN STREET		208.1		208.1			10.0	
TOPEKA STREET		411.1		429.2			20.0	
ATCHISON STREET		110.2		133.6			20.0	
1ST STREET	23.2		52.0		40.0		10.0	
2ND STREET			51.2		45.0		10.0	
<b>SW QUADRANT:</b>								
GRANT STREET			76.1		97.5		10.0	
LINCOLN STREET			62.4		167.5		20.0	
WILLOW STREET			147.9		189.5		20.0	
CHESTNUT STREET			171.6		220.0		20.0	
CEDAR STREET			79.2		166.5		20.0	
TOPEKA STREET		407.8		464.7			20.0	
ATCHISON STREET		266.5		283.9			20.0	
1ST STREET			64.0		147.5		20.0	
2ND STREET			85.2		186.4		20.0	
3RD STREET			40.0		50.0		10.0	
<b>OTHER:</b>								
CROSSWALK OUTSIDE OF TOWN		121.6			142.0		20.0	
E. VIA GHIGLERI STREET	38	52.0			75.0	34	10.0	
LT/RT STA 566+70 AT ALLEY		224.0			224.0		48.0	
<b>SUBTOTAL</b>	61.2	4167.0	1760.5	3601.2	3297.5	34	859.1	
<b>SUBTOTAL FROM CITY PAID SIDEWALK</b>		6081.0	3447.3	6081.0	4190.8			22
<b>GRAND TOTAL</b>	61	10248	5208	9682	7488	34	859	22

REVISIED SHEET 6-4-13

FILE NAME * 68982.dgn	USER NAME * ghudman	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SCHEDULE OF QUANTITIES</b>			F.A.S. RTE. 2361	SECTION 101 RS-4; 102 RS-5	COUNTY MARSHALL	TOTAL SHEETS 51	SHEET NO. 11
PLOT SCALE * 40.0000' / 1" =	CHECKED -	REVISED -	SCALE:					SHEET 11	OF 51	SHEETS STA.	TO STA.	CONTRACT NO. 68982
Default	PLOT DATE * 4/30/2013	DATE -	REVISED -		ILLINOIS FED. AID PROJECT							