

CITY PARTICIPATION SIDEWALK										
LOCATION			LENGTH	EXIST. WIDTH	PROP. WIDTH	SIDEWALK REMOVAL	SIDEWALK REMOVAL SPECIAL	PCC SIDEWALK SPECIAL	PCC SIDEWALK 4"	POROUS GRANULAR EMBANKMENT SPECIAL (2")
						100% city	100% city	80% state 20% city	80% state 20% city	80% State 20% City
			FT	FT	FT.	SQ FT	SQ FT	SQ FT	SQ FT	CU YD
LT. 554+70	TO	LT. 557+70	133	5.75	5.75	764.8			764.8	
RT. 557+70	TO	RT. 561+50	288	3.9	5	1123.2			1,440.0	
LT. 557+70	TO	LT. 558+34	64	5.75	5.75		368.0	368.0		
LT. 560+03	TO	LT. 561+27	124	5.75	5.75		713.0	713.0		
RT. 561+50	TO	RT. 565+00	295	3.9	5	1150.5			1,475.0	
RT. 565+00	TO	RT. 566+05	105	7	7		581.0	581.0		
LT. 568+70	TO	LT. 572+40	269.2	13	13		3,499.6	3,499.6		21.6
RT. 574+60	TO	RT. 576+00	139.3	6.6	6.6		919.4	919.4		
RT. 582+37	TO	RT. 583+40	102.2	4	5	408.8			511.0	
<b>TOTAL</b>						<b>3447</b>	<b>6081</b>	<b>6081</b>	<b>4191</b>	<b>22</b>

PCC DRIVEWAY PAVT 7"			
LOCATION	LENGTH (FT)	WIDTH (FT)	AREA (SQ YD)
RT ALLEY	15.0	7.0	11.7
POST OFFICE	15.0	7.0	11.7
CHURCH	15.0	8.0	13.3
<b>TOTAL</b>			<b>36.7</b>

\*NOTE: USE D4 STANDARD 423111

CONCRETE PAD			
LOCATION	LENGTH (FT)	WIDTH (FT)	AREA (SQ YD)
POST OFFICE	3.0	3.0	1.0
<b>TOTAL</b>			<b>1.0</b>

PAVEMENT REMOVAL SCHEDULE	
LOCATION	AREA
TOPEKA AND IL 117 (MAIN) NE CORNER	34.5
TOPEKA AND IL 117 (MAIN) SE CORNER	20.4
TOPEKA AND IL 117 (MAIN) SW CORNER	34.7
<b>TOTAL</b>	<b>89.6</b>

LOCATION			TOPSOIL FURNISH & PLACE, VAR. DEPTH	EARTH EXCAVATION	EARTH EXCAVATION (WIDENING)	SEEDING CLASS 1A	NITROGEN FERTILIZER NUTRIENTS	PHOSPHORUS FERTILIZER NUTRIENTS	POTASSIUM FERTILIZER NUTRIENTS	EROSION CONTROL BLANKET
			SQ YD	CU YD	CU YD	ACRES	LBS	LBS	LBS	SQ YD
STA 547+00	TO	STA 551+00	248.7			0.05	4.6	4.6	4.6	248.7
STA 551+00	TO	STA 554+70	160.4	2.3		0.03	3.0	3.0	3.0	160.4
STA 554+70	TO	STA 557+70	722.0	1.0		0.15	13.4	13.4	13.4	722.0
STA 557+70	TO	STA 561+50	754.7	1.1		0.16	14.0	14.0	14.0	754.7
STA 561+50	TO	STA 565+00	1063.7	0.4		0.22	19.8	19.8	19.8	1063.7
STA 565+00	TO	STA 568+70								
STA 568+70	TO	STA 572+40								
STA 572+40	TO	STA 576+00	60.1	0.7		0.01	1.1	1.1	1.1	60.1
STA 576+00	TO	STA 579+80	153.4	1.8		0.03	2.9	2.9	2.9	153.4
STA 579+80	TO	STA 583+40	381.1	0.7		0.08	7.1	7.1	7.1	381.1
STA 587+00	TO	STA 602+77	37.5	0.3		0.01	0.7	0.7	0.7	37.5
STA 602+77	TO	STA 616+82	123.6	0.6		0.03	2.3	2.3	2.3	123.6
<b>SHOULDERS (LT/RT)</b>										
STA 530+24	TO	STA 530+89			4.8					
STA 534+89	TO	STA 544+25			69.3					
STA 547+00	TO	STA 547+50			3.7					
STA 547+50	TO	STA 551+00			25.9					
STA 551+00	TO	STA 557+40			47.4					
STA 557+40	TO	STA 581+11			175.6					
STA 581+11	TO	STA 582+01			6.7					
STA 582+01	TO	STA 583+40			10.3					
RT. STA 585+00.5	TO	RT. STA 586+09			8.0					
<b>TOTAL</b>			<b>3705.2</b>	<b>8.8</b>	<b>351.8</b>	<b>0.8</b>	<b>68.9</b>	<b>68.9</b>	<b>68.9</b>	<b>3705.2</b>

△ REVISED SHEET 6-4-13

FILE NAME : 68982.dgn	USER NAME : ghidnoom	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES			F.A.S 2381	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
Default		DRAWN -	REVISED -		SCALE:	SHEET 12	OF 51 SHEETS	STA.	10 STA.	MARSHALL	51	12
		CHECKED -	REVISED -		CONTRACT NO. 68982							
		DATE -	REVISED -		ILLINOIS FED. AID PROJECT							