

MODIFIED URETHANE PAVEMENT MARKING - LINE 4"						
CENTERLINE (YELLOW)				NO PARKING AREA (YELLOW)		
STATION	LENGTH FOOT	SKIP DASH FOOT	SOLID FOOT	STATION	LOCATION**	FOOT
STA. 482+98 TO STA. 520+73*	3775	943.8		LT. STA. 557+70 TO LT. STA. 561+50	1	94
STA. 520+73 TO STA. 530+00	927	231.8	927.0		2	60.4
STA. 530+00 TO STA. 547+13	1713		3426.0		3	60.2
STA. 547+13 TO STA. 552+41*	528	132.0	528.0		4	96
STA. 552+41 TO STA. 568+70	1629	407.3		RT. STA. 557+70 TO RT. STA.	5	122.3
STA. 568+70 TO STA. 667+98	9928	2482.0			6	122.3
<b>TOTAL</b>		<b>9,078</b>		RT. STA. 561+50 TO RT. STA.	7	122.3
					8	122.3
				LT. STA. 561+50 TO LT. STA.	9	122.3
					10	122.3
				LT. STA. 565+00 TO LT. STA. 568+70	11	94
					12	69.5
					13	110.9
					14	104.6
				RT. STA. 565+00 TO RT. STA. 568+70	15	150.5
					16	88.5
					17	80.3
					18	60.2
					19	135.3
				LT. STA. 568+70 TO LT. STA.	20	76.4
					21	108.8
				RT. STA. 568+70 TO RT. STA.	22	91.5
					23	97.2
				LT. STA. 572+40 TO LT. STA. 576+00	24	97.2
					25	59
					26	89.4
					27	103.7
				RT. STA. 572+40 TO RT. STA.	28	104.5
					29	93.5
				RT. STA. 576+00 TO RT. STA.	30	97.3
					31	95.1
<b>GRAND TOTAL</b>		<b>46,170</b>		<b>TOTAL</b>		<b>3,052</b>

\*\*See detail for locations

SHORT TERM PAVEMENT MARKING	
LOCATION	LENGTH (FT)
STA 482+98 TO STA 669+40	185
<b>TOTAL</b>	<b>555</b>

\*NOTE: 3 APPLICATIONS

WORK ZONE PAVT MARKING REMOVAL			
LOCATION	LENGTH (FT)	WIDTH (FT)	AREA (SQFT)
STA 482+98 TO STA 669+40	1850	0.3333	617
530+24 TO STA 586+09	56	0.3333	19
<b>TOTAL</b>			<b>635</b>

\*NOTE: 1 APPLICATION

TRAFFIC CONTROL AND PROTECTION				
LOCATION	STANDARD 701306	STANDARD 701336	STANDARD 701501	STANDARD 701801
	LSUM	LSUM	LSUM	LSUM
ENTIRE JOBSITE	1.0	1.0	1.0	1.0
<b>TOTAL</b>	<b>1.0</b>	<b>1.0</b>	<b>1.0</b>	<b>1.0</b>

LOCATION	ENGINEER'S FIELD OFFICE, TYPE A	MOBILIZATION	CONSTRUCTION LAYOUT	CONSTRUCTING TEST STRIP
	CAL MONTH	LSUM	LSUM	EACH
JOBSITE	3.0	1.0	1.0	1.0
<b>TOTAL</b>	<b>3.0</b>	<b>1.0</b>	<b>1.0</b>	<b>1.0</b>

MODIFIED URETHANE PAVEMENT MARKING - LINE 24"		
STOP BAR (WHITE)		
STATION	LOCATION	WIDTH (FT)
567+95	SANTA FE/IL 117 ( EB)	12.0
568+70	SANTA FE/IL 117 ( WB)	12.0
569+50	MAIN/SANTA FE (NB)	12.0
569+50	IL 117/SANTA FE (SB)	12.0
<b>TOTAL</b>		<b>48.0</b>

△ REVISED 6-4-13

FILE NAME : 68982.dgn	USER NAME : ghdineam	DESIGNED -	REVISIONS -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES	F.A.S. 2351	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
		DRAWN -	REVISIONS -			IL 117	10IRS-4102RS-5	MARSHALL	51	13	
		CHECKED -	REVISIONS -			SCALE:	SHEET 13 OF 51 SHEETS	CONTRACT NO. 68982			
		DATE -	REVISIONS -			ILLINOIS FED. AID PROJECT					