

LANDSCAPE SCHEDULES

| STATION TO                                  | STATION            | AREA (ACRES)      | 28000250<br>TEMPORARY<br>EROSION<br>SEEDING<br>(POUND) | 25000200<br>SEEDING<br>CLASS 2<br>(ACRES) | 25000350<br>SEEDING<br>CLASS 7<br>(ACRES) | 25000400<br>NITROGEN<br>FERT. NUT.<br>(POUNDS) | 25000500<br>PHOSP.<br>FERT. NUT.<br>(POUNDS) | 25000600<br>POTASIU<br>M FERT. NUT.<br>(POUNDS) | 25100635<br>HD EROSION<br>CONTROL<br>BLANKET<br>(SQ. YD.) |
|---|--------------------|-------------------|--|---|---|--|--|---|---|
| <u>TEMPORARY ACCESS ROAD PH. I - STATE</u>  |                    |                   |  |   |   |  |  |   |   |
| 98+00                                       | 99+50              | 0.25              | 25.0   | -   | 0.25                                      | -  | -  | -   | -   |
|   |                    | Sub-Total =       | 25.0   |   | 0.25                                      |  |  |   |   |
| <u>TEMPORARY ACCESS ROAD PH. II - STATE</u> |                    |                   |  |   |   |  |  |   |   |
| 300+00                                      | 308+00             | 0.5               | 50.0   | -   | 0.50                                      | -  | -  | -   | -   |
|   |                    | Sub-Total =       | 50.0   |   | 0.50                                      |  |  |   |   |
| <u>CH 50 - VILLAGE OF MAHOMET</u>           |                    |                   |  |   |   |  |  |   |   |
| LT. 13+75                                   | LT 18+75           | 0.50              | 50.0   | 0.50                                      | 0.50                                      | 45.0   | 45.0   | 45.0  | 2420.0  |
|   | Village of Mahomet | Sub-Total =       | 50.0   | 0.5                                       | 0.5                                       | 45.0   | 45.0   | 45.0  | 2420.0  |
| <u>CH 50 - STATE</u>                        |                    |                   |  |   |   |  |  |   |   |
| 18+75                                       | 20+50              | 0.50              | 50.0   | 0.50                                      | 0.50                                      | 45.0   | 45.0   | 45.0  | 2420.0  |
| 22+75                                       | 34+50              | 1.50              | 150.0  | 1.50                                      | 1.50                                      | 135.0  | 135.0  | 135.0   | 7260.0  |
|   |                    | Sub-Total =       | 200.0  | 2.0                                       | 2.0                                       | 180.0  | 180.0  | 180.0   | 9680.0  |
| <u>GIRL SCOUT CAMP RD. - STATE</u>          |                    |                   |  |   |   |  |  |   |   |
| 98+25                                       | 99+50              | 0.25              | 25.0   | 0.25                                      | 0.25                                      | 22.5   | 22.5   | 22.5  | 1210.0  |
|   |                    | Sub-Total =       | 25.0   | 0.25                                      | 0.25                                      | 22.5   | 22.5   | 22.5  | 1210.0  |
|   |                    | State Sub-Total = | 300.0  | 2.25                                      | 3.0                                       | 203.0  | 203.0  | 203.0   | 10890.0   |
|   |                    | PROJECT TOTAL =   | 350.0  | 2.75                                      | 3.5                                       | 247.5  | 247.5  | 247.5   | 13310.0   |
|   |                    | USE =             | 350.0  | 2.75                                      | 3.5                                       | 248.0  | 248.0  | 248.0   | 13310.0   |

28000305 TEMPORARY DITCH CHECKS - VILLAGE OF MAHOMET

| STATION            | O/S         | LENGTH (FOOT) |
|--------------------|-------------|---------------|
| 13+78              | 42.0 LT.    | 10.0          |
| 14+75              | 47.0 LT.    | 10.0          |
| 15+75              | 50.0 LT.    | 10.0          |
| 16+75              | 57.0 LT.    | 10.0          |
| 17+75              | 66.0 LT.    | 10.0          |
| Village of Mahomet | Sub-total = | 50.0          |

28000305 TEMPORARY DITCH CHECKS - STATE

| STATION | O/S             | LENGTH (FOOT) |
|---------|-----------------|---------------|
| 23+35   | 125.0 LT.       | 10.0          |
| 24+85   | 95.0 LT.        | 10.0          |
| 26+45   | 81.0 LT.        | 10.0          |
| 27+77   | 48.0 RT.        | 10.0          |
| 30+00   | 25.0 RT.        | 10.0          |
| 30+00   | 42.0 LT.        | 10.0          |
| 30+50   | 25.0 RT.        | 10.0          |
| 30+64   | 44.0 LT.        | 10.0          |
| 30+95   | 29.0 RT.        | 10.0          |
| State   | Sub-Total =     | 90.0          |
|         | PROJECT TOTAL = | 140.0         |

28000500 INLET AND PIPE PROTECTION - VILLAGE OF MAHOMET

| STATION            | O/S         | EACH |
|--------------------|-------------|------|
| 15+25              | 27.0 LT.    | 1.0  |
| 16+50              | 27.0 LT.    | 1.0  |
| 18+00              | 27.0 LT.    | 1.0  |
| Village of Mahomet | Sub-Total = | 3.0  |

28000500 INLET AND PIPE PROTECTION - STATE

| STATION | O/S             | EACH |
|---------|-----------------|------|
| 18+00   | 13.0 RT.        | 1.0  |
| 19+40   | 25.0 LT.        | 1.0  |
| 19+40   | 17.0 RT.        | 1.0  |
| 23+50   | 25.0 LT.        | 1.0  |
| 23+50   | 17.0 RT.        | 1.0  |
| 25+00   | 29.0 LT.        | 1.0  |
| 25+00   | 15.0 RT.        | 1.0  |
| 26+50   | 13.0 RT.        | 1.0  |
| 26+62   | 30.0 LT.        | 1.0  |
| 28+00   | 13.0 RT.        | 1.0  |
| 30+86   | 28.0 LT.        | 1.0  |
| 30+97   | 15.0 LT.        | 1.0  |
| 32+41   | 35.0 LT.        | 1.0  |
| 32+41   | 30.0 LT.        | 1.0  |
| State   | Sub-Total =     | 14.0 |
|         | PROJECT TOTAL = | 17.0 |

28000315 AGGREGATE DITCH CHECKS

| STATION         | O/S      | TON  |
|-----------------|----------|------|
| 32+94           | 54.0 LT. | 3.0  |
| 33+13           | 60.0 LT. | 3.0  |
| 33+32           | 65.0 LT. | 3.0  |
| 33+53           | 66.0 LT. | 3.0  |
| 33+85           | 65.0 LT. | 3.0  |
| 34+05           | 61.0 LT. | 3.0  |
| 34+25           | 57.0 LT. | 3.0  |
| PROJECT TOTAL = |          | 21.0 |

28000400 PERIMETER EROSION BARRIER - VILLAGE OF MAHOMET

| STATION TO         | STATION     | FOOT  |
|--------------------|-------------|-------|
| LT. 13+75          | 18+75       | 511.0 |
| Village of Mahomet | Sub-total = | 511.0 |

28000400 PERIMETER EROSION BARRIER - STATE

| STATION TO | STATION         | FOOT   |
|------------|-----------------|--------|
| LT. 18+75  | 20+30           | 243.0  |
| RT. 18+03  | 20+34           | 288.0  |
| LT. 20+67  | 21+16           | 60.0   |
| LT. 22+13  | 34+50           | 1209.0 |
| RT. 22+41  | 34+50           | 971.0  |
| State      | Sub-Total =     | 2771.0 |
|            | PROJECT TOTAL = | 3282.0 |