

DRAIN SCHEDULE

STRUCTURE	STATION	O/S	RIM ELEV.	INVERT ELEV.	542D1081	542D0223	54213447		60100945	60405900	60600095	60900515	60237420	60240215	60240324	550A0090	550A2340	54213663
					P. CULVERT	P. CULVERT	END SECTION	END SECTION	PIPE DRAINS	GRATES & COVERS	CLASS SI	CONC. THRUST	INLET A	INLET B	INLET B	S. S. CLASS A	S. S. R. GASK.	CONC. END
					CLASS D	CLASS D	12" (EACH)	18" (EACH)	12" (FOOT)	T2B (EACH)	CONC. OUTLET (CU. YD.)	(EACH)	(EACH)	(EACH)	(EACH)	TYPE 1, 18" (FOOT)	TYPE 1, 18" (FOOT)	SECT. 18" (EACH)
CURB OUTLET (STANDARD)	14+99	LT.	-	-	-	-	-	-	-	-	4.12	-	-	-	-	-	-	-
1	15+25	LT.	728.45	723.86	-	-	-	-	-	-	-	-	-	-	1.0	21.0	-	1.0
2	16+50	LT.	733.79	729.73	-	-	-	-	-	-	-	-	-	-	1.0	125.0	-	-
PIPE CULVER	33+62	LT.	-	-	16.0	-	-	-	-	-	-	-	-	-	-	-	-	-
Village of Mahomet Sub-Total =					16.0	-	-	-	-	-	-	-	-	-	2.0	146.0	-	1.0
3	18+00	LT.	741.37	736.87	-	-	-	-	-	-	-	-	-	-	1.0	150.0	-	-
CURB OUTLET (TYPE 2)	18+00	RT.	-	739.45	-	-	-	-	44.0	1.0	1.62	1.0	-	-	-	-	-	-
4	19+40	LT.	749.67	746.02	-	-	1.0	-	68.0	-	-	1.0	1.0	-	-	-	-	-
5	19+40	RT.	749.42	745.77	-	-	-	-	65.0	-	-	1.0	1.0	-	-	-	-	1.0
6	23+50	LT.	758.51	754.86	-	-	1.0	-	97.0	-	-	1.0	1.0	-	-	-	-	1.0
7	23+50	RT.	758.26	754.61	-	-	-	-	94.0	-	-	1.0	1.0	-	-	-	-	-
9	25+00	LT.	757.02	753.37	-	-	1.0	-	64.0	-	-	1.0	1.0	-	-	-	-	1.0
8	25+00	RT.	756.89	753.24	-	-	-	-	60.0	-	-	1.0	1.0	-	-	-	-	-
10	26+50	RT.	755.51	751.86	-	-	-	-	50.0	-	-	1.0	1.0	-	-	-	-	1.0
CURB OUTLET (TYPE 2)	26+62	LT.	-	752.89	-	-	1.0	-	64.0	1.0	1.62	1.0	-	-	-	-	-	-
13	28+00	RT.	754.10	751.50	-	-	1.0	-	24.0	-	-	-	1.0	-	-	-	-	-
11	30+85	RT.	745.68	741.20	-	-	-	-	-	-	-	-	-	1.0	-	150	-	-
CURB OUTLET (TYPE 2)	30+97	RT.	745.38	743.72	-	-	1.0	-	14.0	1.0	1.62	-	-	-	-	-	-	-
PIPE CULVER	31+00	RT.	-	-	-	78.0	-	2.0	-	-	-	-	-	-	-	-	-	-
12	32+41	LT.	-	735.00	-	-	-	-	-	-	-	-	1.0	-	35.0	-	-	1.0
CURB OUTLET (TYPE 2)	32+41	LT.	-	737.53	-	-	-	-	5.0	1.0	1.62	-	-	-	-	-	-	-
State Sub-Total =					-	78.0	6.0	2.0	649.0	4.0	6.5	9.0	8.0	1.0	2.0	185.0	150.0	5.0
PROJECT TOTAL =					16.0	78.0	6.0	2.0	649.0	4.0	7.0	9.0	8.0	1.0	4.0	331.0	150.0	6.0

542D0241 PIPE CULVERT, CLASS D, TYPE 1 36"

FAI-74

STATION	O/S	INVERT	TO	STATION	O/S	INVERT	PIPE LENGTH
1548+06	84.85' LT.	730.01		1549+30	87.85' LT.	733.18	124.0

PROJECT TOTAL = 124.0