

SCHEDULE OF QUANTITIES

40600982 HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT					
LOCATION	STATION	TO	STATION	WIDTH (FOOT)	AREA (SQ YD)
MAINLINE QUANTITIES					
BEGINNING OF SECTION	372+12.50	TO	372+80.00	20.0	150.0
APPROACH TO SN 010-0107	389+17.50	TO	389+85.00	VARIES	176.0
DEPARTURE TO SN 010-0107	390+31.50	TO	390+99.00	VARIES	180.0
END OF SECTION	424+98.80	TO	425+66.30	20.0	150.0
MAINLINE TOTAL =					656.0

X4400196 HOT-MIX ASPHALT SURFACE REMOVAL, SPECIAL					
LOCATION	STATION	TO	STATION	WIDTH (FOOT)	AREA (SQ YD)
INCIDENTAL QUANTITIES					
SIDEROAD	373+52.24	RT		VAR	107.1
SIDEROAD	373+53.02	LT		VAR	51.9
PRIVATE ENTRANCE	398+51.30	RT		VAR	36.5
INCIDENTAL TOTAL =					195.5
USE =					196.0

48102100 AGGREGATE WEDGE SHOULDER, TYPE B									
LOCATION	STATION	TO	STATION	LENGTH (FOOT)	AVG. WIDTH (FOOT)	AREA (SQ YD)	AVERAGE THICKNESS (INCHES)	48102100 AGG WEDGE SHLDR, TYPE B (TON)	
MAINLINE QUANTITIES									
	RT	372+12.50	TO RT	389+85.00	1,772.5	3.0	590.8	2.625	77.5
	LT	372+12.50	TO LT	389+85.00	1,772.5	3.0	590.8	2.625	77.5
	RT	390+31.50	TO RT	425+66.30	3,534.8	3.0	1,178.3	2.625	154.6
	LT	390+31.50	TO LT	425+66.30	3,534.8	3.0	1,178.3	2.625	154.6
MAINLINE TOTAL =									464.4
INCIDENTAL QUANTITIES									
SIDEROAD	RT	373+52.24			57.0	2.5	15.8	2.625	2.1
SIDEROAD	LT	373+53.02			32.0	2.5	8.9	2.625	1.2
P.E.	RT	398+51.30			30.0	2.5	8.3	2.625	1.1
MBTO	LT	398+84.00			VARIES	VARIES	29.2	2.625	3.8
INCIDENTAL TOTAL =									8.2
TOTAL =									472.6
USE =									473.0