

# SCHEDULE OF QUANTITIES

DEWITT COUNTY																																																					
72000100															7200200										73000100																												
SIGN PANEL-TYPE 1															SIGN PANEL-TYPE 2																																						
LOC.	U/R	INTERCHANGE	RAMP	SIGN DET.	STOP (R1-1)					WRONG WAY (R5-1A)			ONE WAY (R6-1L/R)		NO RIGHT TURN (R3-1)		NO LEFT TURN (R3-2)			DIR. ARROW (M62-A)		SIGN SUPPORT PANEL	SIGN PANEL TY-1 TOTAL QUANTITY	DO NOT ENTER (R5-1)			FREEWAY ENT. (D13-3)			SIGN PANEL TY-2 TOTAL QUANTITY	WOOD SIGN SUPPORT																						
					9.0 SQ FT PER PANEL		POST LENGTH			8.75 SQ FT PANEL		POST LENGTH 13.5 FT	6.75 SQ FT PANEL		9.0 SQ FT PANEL	9.0 SQ FT PANEL		POST LENGTH 14 FT	2.2 SQ FT PANEL		1.65 SQ FT			SQ FT	16.0 SQ FT PANEL		POST LENGTH 15.0 OR 16.5 FT	10.0 SQ FT PANEL				POST LENGTH 14.75 FT																					
EACH	SQ FT	LT	CTR	RT	EACH	SQ FT	FT	EACH	SQ FT	FT	EACH	SQ FT	EACH	SQ FT	EACH	SQ FT	FT	EACH	SQ FT	FT	EACH	SQ FT	FT	EACH	SQ FT	FT	EACH	SQ FT	FT	SQ FT	FT																						
1	R	I-74 & IL 54	WB	A	2.0	18.0		14.5	15.5	4.0	35.0	54.0	4.0	27.0	1.0	9.0	2.0	18.0	28.0			9.9	116.9	2.0	32.0	30.0				32.0	142.0																						
			EB	A	2.0	18.0		14.5	15.5	4.0	35.0	54.0	4.0	27.0	1.0	9.0	2.0	18.0	28.0			9.9	116.9	2.0	32.0	30.0				32.0	142.0																						
																						RURAL =		234.0																								RURAL =		64.0		284.0	
																						URBAN =		0.0																								URBAN =		0.0		0.0	
																						TOTAL =		234.0																								TOTALS =		64.0		284.0	

U-URBAN  
R-RURAL  
RT-RIGHT SIDE OF RAMP  
CTR-CENTER ISLAND IN RAMP  
LT-LEFT SIDE OF RAMP

DOUGLAS COUNTY																																																					
72000100															7200200										73000100																												
SIGN PANEL-TYPE 1															SIGN PANEL-TYPE 2																																						
LOC.	U/R	INTERCHANGE	RAMP	SIGN DET.	STOP (R1-1)					WRONG WAY (R5-1A)			ONE WAY (R6-1L/R)		NO RIGHT TURN (R3-1)		NO LEFT TURN (R3-2)			DIR. ARROW (M62-A)		SIGN SUPPORT PANEL	SIGN PANEL TY-1 TOTAL QUANTITY	DO NOT ENTER (R5-1)			FREEWAY ENT. (D13-3)			SIGN PANEL TY-2 TOTAL QUANTITY	WOOD SIGN SUPPORT																						
					9.0 SQ FT PER PANEL		POST LENGTH			8.75 SQ FT PANEL		POST LENGTH 13.5 FT	6.75 SQ FT PANEL		9.0 SQ FT PANEL	9.0 SQ FT PANEL		POST LENGTH 14 FT	2.2 SQ FT PANEL		1.65 SQ FT			SQ FT	16.0 SQ FT PANEL		POST LENGTH 15.0 OR 16.5 FT	10.0 SQ FT PANEL				POST LENGTH 14.75 FT																					
EACH	SQ FT	LT	CTR	RT	EACH	SQ FT	FT	EACH	SQ FT	FT	EACH	SQ FT	EACH	SQ FT	EACH	SQ FT	FT	EACH	SQ FT	FT	EACH	SQ FT	FT	EACH	SQ FT	FT	EACH	SQ FT	FT	SQ FT	FT																						
1	R	I-57 & IL 133	SB	A	2.0	18.0		14.5	15.5	4.0	35.0	54.0	4.0	27.0	1.0	9.0	2.0	18.0	28.0			9.9	116.9	2.0	32.0	30.0				32.0	142.0																						
			NB	A	2.0	18.0		14.5	15.5	4.0	35.0	54.0	4.0	27.0	1.0	9.0	2.0	18.0	28.0			9.9	116.9	2.0	32.0	30.0				32.0	142.0																						
2	R	I-57 & US 36	SB	I						4.0	35.0	54.0	2.0	13.5						1.0	2.2	9.9	60.6	2.0	32.0	31.5	1.0	10.0	14.75	42.0	100.25																						
			NB	I						4.0	35.0	54.0	2.0	13.5						1.0	2.2	9.9	60.6	2.0	32.0	31.5	1.0	10.0	14.75	42.0	100.25																						
																						RURAL =		355.0																								RURAL =		148.0		485.0	
																						URBAN =		0.0																								URBAN =		0.0		0.0	
																						TOTAL =		355.0																								TOTALS =		148.0		485.0	

U-URBAN  
R-RURAL  
RT-RIGHT SIDE OF RAMP  
CTR-CENTER ISLAND IN RAMP  
LT-LEFT SIDE OF RAMP

\*SIGN & PVT MRK UPGRADES 2013-1