



WORK ZONE SPEED LIMIT SIGNS AND FLAGGER SIGNS SHALL BE MOVED AS NECESSARY TO MAINTAIN THE REQUIRED SPACING BETWEEN THE SIGNS AND THE WORKERS IN EACH SEPARATE WORK ACTIVITY. WORK ZONE SPEED LIMIT 55 PHOTO ENFORCED SIGN SHALL BE OMITTED WHEN THE WORK AREA DICTATES PLACEMENT OF THE SIGN ARRAY WITHIN 500' (150 M) OF THE END WORK ZONE SPEED LIMIT SIGN.

NOTE

- ① TEMPORARY PAVEMENT MARKING TAPE SHALL BE PLACED THROUGH OUT THE TAPER AND ALONGSIDE THE WORK AREA. THE RIGHT EDGE AND CENTERLINE SHALL BE WHITE AND THE LEFT EDGE SHALL BE YELLOW.
- ② BARRIER WALL/GUARDRAIL MARKERS AT 25' (7.6M) MARKERS ON RIGHT SHALL BE CRYSTAL AND MARKERS ON THE LEFT SHALL BE AMBER. SEE STANDARDS 704001 AND 635001

SYMBOLS

- WORK AREA
- SIGN ON PORTABLE OR PERMANENT SUPPORT
- TYPE II BARRICADE, DRUM, OR VERTICAL BARRICADE WITH STEADY BURN MONODIRECTIONAL LIGHT
- IMPACT ATTENUATOR
- BARRIER WALL/GUARDRAIL MARKER

FILE NAME *	USER NAME = sparhgw	DESIGNED - RTS	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	TRAFFIC CONTROL AND PROTECTION STANDARD 701423 (SPECIAL)			F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
c:\p\work\p\dos\spargw\d0216368\067	505-sh-TCP.dgn	DRAWN -	REVISED -		SCALE:	SHEET 3 OF 3 SHEETS	STA.	TO STA.	55	68-2WS-2	MONTGOMERY	124	61
Default	PLOT SCALE = 60.0000' / in.	CHECKED -	REVISED -		CONTRACT NO. 72505								
	PLOT DATE = May-10-2013 02:46:08PM	DATE -	REVISED -		ILLINOIS FED. AID PROJECT								