

SUMMARY OF QUANTITIES				CONSTR. CODE	CONSTR. CODE	CONSTR. CODE
				0005	0005	0021
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	ROADWAY	PARKING	SIDEWALK
				80% FEDERAL		80% FEDERAL
				20% STATE	50% STATE	20% CITY
					50% CITY	
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	157	157		
44000600	SIDEWALK REMOVAL	SO FT	179.0			179.0
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	18			18
44200202	PAVEMENT PATCHING, TYPE II, 17 INCH	SQ YD	621	621		
44200204	PAVEMENT PATCHING, TYPE III, 17 INCH	SO YD	79	79		
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	1967	1967		
48203100	HOT-MIX ASPHALT SHOULDERS	TON	3460	3460		
48203023	HOT-MIX ASPHALT SHOULDERS, 6 1/2"	SO YD	15964	15964		
50105220	PIPE CULVERT REMOVAL	FOOT	24	24		
542D0220	PIPE CULVERT, CLASS D, TYPE 1, 15"	FOOT	32	32		
542D0229	PIPE CULVERT, CLASS D, TYPE 1, 24"	FOOT	32	32		
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	18.0			18.0
* 63000001	STEEL PLATE BEAM GUARDRAIL TYPE A, 6 FOOT POSTS	FOOT	550.0	550.0		
* 63000025	STEEL PLATE BEAM GUARDRAIL, ATTACHED TO STRUCTURE	FOOT	75.0	75.0		
* 63000360	LONG-SPAN GUARDRAIL OVER CULVERT, 18 FT 9 IN SPAN	FOOT	338.0	338.0		

\*SPECIALTY ITEM

FILE NAME : c:\pwork\pavdot\parksg-1d82347601067	USER NAME : sparksgw BE03-ehs-500.dgn	DESIGNED - ML DRAWN - ML	REVISED - REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>			F.A.P. RTE. 315	SECTION (HRS-2, (I24)RS-3, (I16)RS	COUNTY MASON	TOTAL SHEETS 62	SHEET NO. 4
PLOT SCALE : 100.0000 1" = 100'		CHECKED -	REVISED -		SCALE:	SHEET NO. 2 OF 5 SHEETS	STA.	TO STA.	CONTRACT NO. 72E03			
PLOT DATE : Dec-14-2012 02:33:53PM		DATE - 8-1-12	REVISED -		ILLINOIS FED. AID PROJECT							