

HMA SHOULDER TREATMENT, RIGHT SIDE													
LOCATION			SHOULDER WIDTH	DISTANCE OF RUN	SHOULDER AREA	SHOULDER AREA	HMA SHOULDER, 6 1/2"	HMA SHOULDER, 1 1/2" (top lift)	HMA SHOULDER, 2 1/4" (top lift)	AGG PRIME COAT	BIT. MATERIAL (PRIME COAT)	EXCAVATING & GRADING	
			(FOOT)	(FOOT)	(SQ FT)	(SQ YD)	(SQ YD)	(TON)	(TON)	ONE APPLICATION	ONE APPLICATION	EXISTING SHOULDER	
BEGINNING OF PROJECT US 136													
STA 426+00.00	TO	STA 430+69.17	4.0	469.17	1876.68	208.52	208.52	17.52		0.42	0.08	4.69	
STA. EQUATION: STA. 430+69.17(BK) = STA. 0+00 (AHD)													
STA 0+00.00	TO	STA 2+33.00	4.0	233.00	932.00	103.56	103.56	8.70		0.21	0.04	2.33	
IL 29 (SOUTH LEG)			4.0	CADD	1219.00	135.44	135.44	11.38		0.27	0.05	3.40	
STA 4+28.00	TO	STA 10+00.00	4.0	572.00	2288.00	254.22	254.22	21.35		0.51	0.10	5.72	
STA 10+00.00	TO	STA 27+00.00	4.0	1700.00	6800.00	755.56	755.56	63.47		1.51	0.29	17.00	
STA 27+00.00	TO	STA 44+00.00	4.0	1700.00	6800.00	755.56	755.56	63.47		1.51	0.29	17.00	
STA 44+00.00	TO	STA 55+67.00	4.0	1167.00	4668.00	518.67	518.67	43.57		1.04	0.20	11.67	
TR 3600E													
STA 56+13.00	TO	STA 61+00.00	4.0	487.00	1948.00	216.44	216.44	18.18		0.43	0.08	4.87	
STA 61+00.00	TO	STA 65+50.00	4.0	450.00	1800.00	200.00	200.00	16.80		0.40	0.08	4.50	
STA 65+50.00	TO	STA 66+00.00	4.0 - 8.5	50.00	313.00	34.78	34.78	2.92		0.07	0.01	0.50	
STA 66+00.00	TO	STA 70+64.00	8.5	464.00	3944.00	438.22	438.22	36.81		0.88	0.17	4.64	
STA 70+64.00	TO	STA 71+14.00	8.5 - 4.0	50.00	313.00	34.78	34.78	2.92		0.07	0.01	0.50	
STA 71+14.00	TO	STA 78+00.00	4.0	686.00	2744.00	304.89	304.89	25.61		0.61	0.12	6.86	
STA 78+00.00	TO	STA 95+00.00	4.0	1700.00	6800.00	755.56	755.56	63.47		1.51	0.29	17.00	
STA 95+00.00	TO	STA 97+80.00	4.0	280.00	1120.00	124.44	124.44	10.45		0.25	0.05	2.80	
STA 97+80.00	TO	STA 98+30.00	4.0 - 7.5	50.00	287.50	31.94	31.94	2.68		0.06	0.01	0.50	
STA 98+30.00	TO	STA 101+20.00	7.5	290.00	2175.00	241.67	241.67	20.30		0.48	0.09	2.90	
STA 101+20.00	TO	STA 101+70.00	7.5 - 4.0	50.00	287.50	31.94	31.94	2.68		0.06	0.01	0.50	
STA 100+70.00	TO	STA 112+00.00	4.0	1130.00	4520.00	502.22	502.22	42.19		1.00	0.19	11.30	
STA 112+00.00	TO	STA 120+90.00	4.0	890.00	3560.00	395.56	395.56	33.23		0.79	0.15	8.90	
TR 3720E													
STA 121+33.00	TO	STA 129+00.00	4.0	767.00	3068.00	340.89	340.89	28.63		0.68	0.13	7.67	
STA 129+00.00	TO	STA 132+30.00	4.0	330.00	1320.00	146.67	146.67	12.32		0.29	0.06	3.30	
TR 3740E													
STA 132+81.00		STA 134+12.27	4.0	131.27	525.08	58.34	58.34	4.90		0.12	0.02	1.31	
RAILROAD OMISSION													
STA 134+82.38	TO	STA 146+00.00	4.0	1117.62	4470.48	496.72	496.72	41.72		0.99	0.19	11.18	
STA 146+00.00	TO	STA 149+00.00	4.0	300.00	1200.00	133.33	133.33	11.20		0.27	0.05	3.00	
STA 149+00.00	TO	STA 160+52.00	4.0	1152.00	4608.00	512.00	512.00	43.01		1.02	0.19	11.52	
TR 3800E (CH 9)													
STA 160+76.00	TO	STA 163+00.00	4.0	224.00	896.00	99.56	99.56	8.36		0.20	0.04	2.24	
STA 163+00.00	TO	STA 164+46.00	4.0	146.00	584.00	64.89	64.89	5.45		0.13	0.02	1.46	
STA 164+58.00	TO	STA 166+10.00	VARIES	152.00	931.00	103.44	103.44	8.69		0.21	0.04	1.52	
STA 166+10.00	TO	STA 169+50.00	VARIES	340.00	2416.00	268.44			33.82				
STA 169+50.00	TO	STA 180+00.00	8.8 AVG	1050.00	9240.00	1026.67			129.36				
STA 180+00.00	TO	STA 197+00.00	9.3 AVG.	1700.00	15810.00	1756.67			221.34				
STA 197+00.00	TO	STA 212+56.00	9.0 AVG	1556.00	14004.00	1556.00			196.06				
TR 3900E													
STA 213+36.00	TO	STA 214+00.00	10.0 AVG.	64.00	640.00	71.11			8.96				
STA 214+00.00	TO	STA 231+00.00	10.0 AVG.	1700.00	17000.00	1888.89			238.00				
STA 231+00.00	TO	STA 247+37.00	VARIES	1637.00	15925.00	1769.44			222.95				
TOTALS =					24785.06	147033.24	16337.03	7999.80	671.98	1050.49	16.00	3.04	170.79

FILE NAME =	USER NAME = sparksgw	DESIGNED - ML	REVISED - RTS	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES				F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
c:\pwork\pwork\sparksgw\10239760\0672E03-sht-schedule.dgn		DRAWN - ML	REVISED -		315	(HRS-3, (124)RS-2, (116)RS	MASON	62	11				
Default	PLOT SCALE = 100.0000' / 1in.	CHECKED - RTS	REVISED -		SCALE: SHEET 4 OF 15 SHEETS STA. TO STA.				CONTRACT NO. 72E03				
	PLOT DATE = Dec-14-2012 02:35:15PM	DATE - 09-26-2012	REVISED -		ILLINOIS FED. AID PROJECT								