

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE						STA. 577+01 TO STA. 590+00 0005			
				RURAL 90% FEDERAL		10% STATE		0014	0014				
				SN 054-0057 SN 054-0058	SN 054-0060 SN 054-0061	SN 054-0062	SN 054-0063 SN 054-0064				SN 054-0065 SN 054-0066 SN 054-0067 SN 054-0068		
28100207	STONE RIPRAP, CLASS A4	TON	605					284			321		
28200200	FILTER FABRIC	SQ YD	1,074					497			577		
31100700	SUBBASE GRANULAR MATERIAL, TYPE A 8"	SQ YD	6,372								6,372		
31100910	SUBBASE GRANULAR MATERIAL, TYPE A 12"	SQ YD	2,433								2,433		
31101400	SUBBASE GRANULAR MATERIAL, TYPE B 6"	SQ YD	934								934		
35300300	PORTLAND CEMENT CONCRETE BASE COURSE 8"	SQ YD	934								934		
35501326	HOT-MIX ASPHALT BASE COURSE, 10 1/2"	SQ YD	5,889								5,889		
35501327	HOT-MIX ASPHALT BASE COURSE, 10 3/4"	SQ YD	9,802			1,027		1,045		1,752	5,978		
35501332	HOT-MIX ASPHALT BASE COURSE, 12"	SQ YD	2,305								2,305		
35501333	HOT-MIX ASPHALT BASE COURSE, 12 1/4"	SQ YD	2,286			1,067		1,219					
35501342	HOT-MIX ASPHALT BASE COURSE, 14 1/2"	SQ YD	1,100						1,100				
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	7			1.0		0.7		0.7	1.8	1.8	1.0
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	181									181	
40600895	CONSTRUCTING TEST STRIP	EACH	1								1		

△ REVISED 6-3-13



JOB # 2236.10  
 FILE NAME = D672E11-shr-500.dgn  
 PLOT SCALE = 28.0000' / IN.  
 PLOT DATE = 3/28/2013

DESIGNED - NAK  
 DRAWN - SJS  
 CHECKED - NAK  
 DATE - 1/4/12

REVISED -  
 REVISED -  
 REVISED -  
 REVISED -

STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET NO. 2 OF 14 SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55	D6 LOGAN CO BR 2011-1	LOGAN	429	5
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT			CONTRACT NO. 72E11	