

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE						
				RURAL 90% FEDERAL		10% STATE		SN 054-0065 SN 054-0066 SN 054-0067 SN 054-0068	SN 054-0069	
				SN 054-0057 SN 054-0058	SN 054-0060 SN 054-0061	SN 054-0062	SN 054-0063 SN 054-0064			0014
50606704	CLEANING AND PAINTING STRUCTURAL STEEL, LOCATION 4	L SUM	1	1						
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	1147,770	194,430	502,390		281,060	161,180	8,710	
50800515	BAR SPLICERS	EACH	8,405	1,538	4,179		2,464	176	48	
51100100	SLOPE WALL 4 INCH	SQ YD	16				16			
51500100	NAME PLATES	EACH	8	2	2		2	2		
52000110	PREFORMED JOINT STRIP SEAL	FOOT	300		128				172	
52100010	ELASTOMERIC BEARING ASSEMBLY, TYPE I	EACH	74	24	14		12	24		
52100020	ELASTOMERIC BEARING ASSEMBLY, TYPE II	EACH	12				12			
52100030	ELASTOMERIC BEARING ASSEMBLY, TYPE III	EACH	14		14					
52100520	ANCHOR BOLTS, 1"	EACH	296	48	56		96	96		
5421D018	PIPE CULVERTS, CLASS D, TYPE 1 18" (TEMPORARY)	FOOT	43						43	
5421D024	PIPE CULVERTS, CLASS D, TYPE 1 24" (TEMPORARY)	FOOT	943						943	
54213447	END SECTIONS 12"	EACH	15		8				7	
54213459	END SECTIONS 24"	EACH	4						4	

△ REVISED 6-3-13



JOB # 2236.10
 FILE NAME # 0672C11-ah1-500.dgn
 PLOT SCALE = 28,0000' / 1"
 PLOT DATE = 3/28/2013

DESIGNED - NAK
 DRAWN - SJS
 CHECKED - NAK
 DATE - 1/4/12

REVISED -
 REVISED -
 REVISED -
 REVISED -

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES
 SCALE: SHEET NO. 6 OF 14 SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55	D6 LOGAN CO BR 2011-1	LOGAN	429	9
CONTRACT NO. 72E11				
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				