

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE					
				RURAL 90%		FEDERAL 10%		STATE	
				SN 054-0057 SN 054-0058	SN 054-0060 SN 054-0061	SN 054-0062	SN 054-0063 SN 054-0064	SN 054-0065 SN 054-0066 SN 054-0067 SN 054-0068	SN 054-0069
				0014	0014	0014	0014	0014	0014
28100207	STONE RIPRAP, CLASS A4	TON	605		284			321	
28200200	FILTER FABRIC	SQ YD	1,074		497			577	
31100700	SUBBASE GRANULAR MATERIAL, TYPE A 8"	SQ YD	6,372					6,372	
31100910	SUBBASE GRANULAR MATERIAL, TYPE A 12"	SQ YD	2,433					2,433	
31101400	SUBBASE GRANULAR MATERIAL, TYPE B 6"	SQ YD	934						934
35300300	PORTLAND CEMENT CONCRETE BASE COURSE 8"	SQ YD	934						934
35501326	HOT-MIX ASPHALT BASE COURSE, 10 1/2"	SQ YD	5,889					5,889	
35501327	HOT-MIX ASPHALT BASE COURSE, 10 3/4"	SQ YD	9,802	1,027	1,045		1,752	5,978	
35501332	HOT-MIX ASPHALT BASE COURSE, 12"	SQ YD	2,305						2,305
35501333	HOT-MIX ASPHALT BASE COURSE, 12 1/4"	SQ YD	2,286	1,067	1,219				
35501342	HOT-MIX ASPHALT BASE COURSE, 14 1/2"	SQ YD	1,100				1,100		
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	6	1.0	0.7		0.7	1.8	1.8
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	181						181
40600895	CONSTRUCTING TEST STRIP	EACH	1					1	



JOB # 2236.10
 FILE NAME # 0672E11-shr-500.dgn
 PLOT SCALE # 28.0000 ' / IN.
 PLOT DATE # 3/28/2013

DESIGNED - NAK
 DRAWN - SJS
 CHECKED - NAK
 DATE - 1/4/12

REVISED -
 REVISED -
 REVISED -
 REVISED -

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET NO. 2 OF 14 SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55	06 LOGAN CD BR 2011-1	LOGAN	429	5
CONTRACT NO. 72E11				
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				