

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE					
				RURAL 90% FEDERAL		10% STATE			
				SN 054-0057 SN 054-0058	SN 054-0060 SN 054-0061	SN 054-0062	SN 054-0063 SN 054-0064	SN 054-0065 SN 054-0066 SN 054-0067 SN 054-0068	SN 054-0069
				0014	0014	0014	0014	0014	0014
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	933						933
40600990	TEMPORARY RAMP	SQ YD	63						63
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	388						388
40603345	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N90	TON	2,190	266	310		329	1,285	
42001420	BRIDGE APPROACH PAVEMENT CONNECTOR (PCC)	SQ YD	1,194	184	536		269	205	
42100200	CONTINUOUSLY REINFORCED PORTLAND CEMENT CONCRETE PAVEMENT 9"	SQ YD	1,298					1,298	
42100615	PAVEMENT REINFORCEMENT	SQ YD	1,298					1,298	
44000100	PAVEMENT REMOVAL	SQ YD	6,695	2,132	250			4,313	
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	616	616					
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	560	560					
44004250	PAVED SHOULDER REMOVAL	SQ YD	18,616	2,381	2,539		3,171	8,310	2,215
44200577	CLASS A PATCHES, TYPE II, 12 INCH	SQ YD	427	27	117		123	160	
44200581	CLASS A PATCHES, TYPE III, 12 INCH	SQ YD	144					144	
44200620	CLASS A PATCHES, TYPE II, 14 INCH	SQ YD	104	48	56				

14



JOB # 2236.10  
 FILE NAME \* 0672E11-ah1-500.dgn  
 PLOT SCALE \* 20,000' / IN.  
 PLOT DATE \* 3/28/2013

DESIGNED - NAK  
 DRAWN - SJS  
 CHECKED - NAK  
 DATE - 1/4/12

REVISED -  
 REVISED -  
 REVISED -  
 REVISED -

STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET NO. 3 OF 14 SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55	D6 LOGAN CO BR 2011-1	LOGAN	429	6
CONTRACT NO. 72E11				
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				