

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE					
				RURAL 90% FEDERAL		10% STATE			
				SN 054-0057 SN 054-0058	SN 054-0060 SN 054-0061	SN 054-0062	SN 054-0063 SN 054-0064	SN 054-0065 SN 054-0066 SN 054-0067 SN 054-0068	SN 054-0069
Z0004552	APPROACH SLAB REMOVAL	SQ YD	2,406	427	600		470	909	
Z0006016	BRIDGE DECK LATEX CONCRETE OVERLAY, 2 3/4 INCHES	SQ YD	1,761						1,761
Z0007103	CONTAINMENT AND DISPOSAL OF LEAD PAINT CLEANING RESIDUES NO. 3	L SUM	1		1				
Z0007104	CONTAINMENT AND DISPOSAL OF LEAD PAINT CLEANING RESIDUES NO. 4	L SUM	1		1				
Z0012146	BRIDGE DECK SCARIFICATION 2 3/4"	SQ YD	1,761						1,761
Z0012754	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SQ FT	624	9	43		11	9	552
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	0.2	0.2		0.2	0.2	0.2
Z0016002	DECK SLAB REPAIR (FULL DEPTH, TYPE II)	SQ YD	32						32
Z0016200	DECK SLAB REPAIR (PARTIAL)	SQ YD	25						25
Z0016702	DETOUR SIGNING	L SUM	1					1	
Z0018002	DRAINAGE SCUPPERS, DS-11	EACH	16		8		8		
Z0021916	SILICONE JOINT SEALER, 3"	FOOT	62			62			
Z0026407	TEMPORARY SHEET PILING	SQ FT	3,618	961	1,904		753		
Z0029090	DIAMOND GRINDING (BRIDGE SECTION)	SQ YD	6,783	1,826			3,241	1,716	

14



JOB \* 2236.10  
 FILE NAME \* 0672E11-ah1-500.dgn  
 PLOT SCALE \* 20.0000' / IN.  
 PLOT DATE \* 3/20/2013

DESIGNED - NAK  
 DRAWN - SJS  
 CHECKED - NAK  
 DATE - 1/4/12

REVISED -  
 REVISED -  
 REVISED -  
 REVISED -

STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET NO. 13 OF 14 SHEETS STA. TO STA.

F.A.T. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55	06 LOGAN CO BR 2011-1	LOGAN	429	16
CONTRACT NO. 72E11				
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				