I-55 PATCHING

LOCATION	NO. OF PATCHES	LENGTH	WIDTH			SS A PATC	_		TIE BARS	SAW CUTS	PATCHING REINFORCEMENT
	174101120			TYPE II	TYPE III	TYPE II	TYPE III	TYPE IV			
		FOOT	FOOT	12 INCH	12 INCH	14 INCH	14 INCH	14 INCH	EAGU	FOOT	00.1/0
		FOOT	FOOT	SQ YD	SQ YD	SQ YD	SQ YD	SQ YD	EACH	FOOT	SQ YD
SN 054-0057	2	6	12	16.00						120	16.00
SN 054-0057	1	8	12	10.67						64	10.67
SN 054-0058	2	6	12			16.00				120	16.00
SN 054-0058	3	8	12			32.00				192	32.00
SN 054-0060	7	6	12			56.00				420	56.00
SN 054-0061	8	6	12	64.00						480	64.00
SN 054-0061	5	8	12	53.33						320	53.33
SN 054-0060	5	12	12				80.00			360	80.00
SN 054-0060	1	25	12					33.33	13	98	33.33
SN 054-0063 & SN 054-0064	4	8	12	42.67						256	42.67
SN 054-0063 & SN 054-0064	10	6	12	80.00						600	80.00
SN 054-0065 & SN 054-0066	20	6	12	160.00		_				1,200	160.00
SN 054-0065 & SN 054-0066	9	12	12		144.00		·			648	144.00
TOTAL				426.67	144.00	104.00	80.00	33.33	13	4,878	788.00

CH 6 PATCHING

LOCATION	NO. OF PATCHES	LENGTH	WIDTH	CLASS B PATCHES, TYPE II, 8 INCH	DOWEL BARS 1 1/2"	SAW CUTS
		FOOT	FOOT	SQ YD	EACH	FOOT
WESTBOUND LANE	36	6	14	336.00	792	1,944
EASTBOUND LANE	44	6	14	410.67	968	2,376
TOTAL	80			746.67	1,760	4,320

LONGITUDINAL JOINT REPAIR

EGITORITA E GOITTI TELI TIIT	
LOCATION	FOOT
CH 6	1,150
TOTAL	1,150

CEC	Cummins Engineering Corporation						
Civil and Structural Engineering							

	JOB = 2236.10	DESIGNED	-	NAK	REVISED -
,	FILE NAME = D672E11-sht-Schedules.dgn	DRAWN	-	SJS	REVISED -
1	PLOT SCALE = 1.8333 ' / IN.	CHECKED	-	NAK	REVISED -
-	PLOT DATE = 3/18/2013	DATE	-	1/4/12	REVISED -

STATE	: OF	ILLINOIS
DEPARTMENT	OF	TRANSPORTATION

CONTRIBUTE OF CHANTITIES						SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	SCHEDULES OF QUANTITIES					D6 LOGAN CO BR 2011-1	LOGAN	429	51
				CONTRACT NO. 72E11					
	SCALE:	SHEET NO. 8 OF 19 SHEETS	STA.	TO STA.	FED. RO	FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT			