

TEMPORARY PAVEMENT MARKING - LINE 5"

LOCATION	SOLID WHITE FOOT	SOLID YELLOW FOOT	WHITE SKIP DASH FOOT	TOTAL FOOT	WORK ZONE PVT MK REM SQ FT
SN 054-0057, 054-0058					
STAGE 1					
NB I-55 MEDIAN EDGE LINE					
STA 553+35.00 TO STA 581+64.00		2,829.00		2,829.00	1,178.75
NB I-55 OUTSIDE EDGE LINE					
STA 571+54.00 TO STA 581+64.00	1,010.00			1,010.00	420.83
SB I-55 MEDIAN EDGE LINE					
STA 572+04.50 TO STA 597+14.00		2,509.50		2,509.50	1,045.63
SB I-55 OUTSIDE EDGE LINE					
STA 572+04.50 TO STA 572+14.00	9.50			9.50	3.96
STAGE 2					
NB I-55 MEDIAN EDGE LINE					
STA 572+80.50 TO STA 580+38.00		757.50		757.50	315.63
NB I-55 OUTSIDE EDGE LINE					
STA 553+35.00 TO STA 580+38.00	2,703.00			2,703.00	1,126.25
SB I-55 MEDIAN EDGE LINE					
STA 573+30.50 TO STA 595+88.00		2,257.50		2,257.50	940.63
SB I-55 OUTSIDE EDGE LINE					
STA 573+30.50 TO STA 580+88.00	757.50			757.50	315.63
SN 054-0060, 054-0061					
STAGE 1					
NB I-55 MEDIAN EDGE LINE					
STA 677+08.20 TO STA 703+63.85		2,655.65		2,655.65	1,106.52
NB I-55 OUTSIDE EDGE LINE					
STA 692+08.20 TO STA 701+55.80	947.60			947.60	394.83
STA 701+55.80 TO STA 704+20.85			68.00	68.00	28.33
STA 704+20.85 TO STA 706+32.00	211.15			211.15	87.98
SB I-55 MEDIAN EDGE LINE					
STA 696+22.25 TO STA 723+00.00		2,677.75		2,677.75	1,115.73
SB I-55 OUTSIDE EDGE LINE					
STA 693+54.00 TO STA 704+83.75	1,129.75			1,129.75	470.73
STA 704+83.75 TO STA 707+62.90			70.00	70.00	29.17
STA 707+62.90 TO STA 708+03.25	40.35			40.35	16.81
RAMP C					
STA 12+52.85 TO STA 17+49.00	496.15			496.15	206.73
STA 12+52.85 TO STA 14+72.00		219.15		219.15	91.31
STAGE 2					
NB I-55 MEDIAN EDGE LINE					
STA 692+56.00 TO STA 705+83.85		1,327.85		1,327.85	553.27
NB I-55 OUTSIDE EDGE LINE					
STA 677+57.00 TO STA 703+63.85	2,606.85			2,606.85	1,086.19
STA 705+54.50 TO STA 706+75.00	120.50			120.50	50.21
RAMP B					
STA 3+49.90 TO STA 6+62.50	312.60			312.60	130.25
STA 5+41.00 TO STA 6+62.50		121.50		121.50	50.63
SB I-55 MEDIAN EDGE LINE					
STA 694+27.25 TO STA 707+54.75		1,327.50		1,327.50	553.13
SB I-55 OUTSIDE EDGE LINE					
STA 696+47.25 TO STA 705+87.60	940.35			940.35	391.81
STA 705+87.60 TO STA 707+13.00			32.00	32.00	13.33
STA 707+13.00 TO STA 722+50.00	1,537.00			1,537.00	640.42
RAMP C					
STA 13+00.00 TO STA 16+45.73	345.73			345.73	144.05
STA 13+00.00 TO STA 15+20.75		220.75		220.75	91.98

CONTINUES NEXT COLUMN

TEMPORARY PAVEMENT MARKING - LINE 5"

LOCATION	SOLID WHITE FOOT	SOLID YELLOW FOOT	WHITE SKIP DASH FOOT	TOTAL FOOT	WORK ZONE PVT MK REM SQ FT
SN 054-0063, 054-0064					
STAGE 1					
NB I-55 MEDIAN EDGE LINE					
STA 261+48.40 TO STA 285+84.40		2,436.00		2,436.00	1,015.00
NB I-55 OUTSIDE EDGE LINE					
STA 276+48.40 TO STA 288+20.40	1,172.00			1,172.00	488.33
SB I-55 MEDIAN EDGE LINE					
STA 278+94.26 TO STA 303+30.26		2,436.00		2,436.00	1,015.00
SB I-55 OUTSIDE EDGE LINE					
STA 276+58.26 TO STA 288+30.26	1,172.00			1,172.00	488.33
STAGE 2					
NB I-55 MEDIAN EDGE LINE					
STA 277+74.40 TO STA 286+94.38		919.98		919.98	383.33
NB I-55 OUTSIDE EDGE LINE					
STA 262+74.38 TO STA 285+84.40	2,310.02			2,310.02	962.51
SB I-55 MEDIAN EDGE LINE					
STA 277+84.26 TO STA 287+04.26		920.00		920.00	383.33
SB I-55 OUTSIDE EDGE LINE					
STA 278+94.26 TO STA 302+04.00	2,309.74			2,309.74	962.39
SN 054-0066, 054-0066, 054-0067, 054-0068					
STAGE 1					
NB I-55 MEDIAN EDGE LINE					
STA 429+75.00 TO STA 482+98.50		5,323.50		5,323.50	2,218.13
NB I-55 OUTSIDE EDGE LINE					
STA 449+75.00 TO STA 479+46.35	2,971.35			2,971.35	1,238.06
STA 479+46.35 TO STA 481+99.80			64.00	64.00	26.67
STA 481+99.80 TO STA 482+98.50	98.70			98.70	41.12
SB I-55 MEDIAN EDGE LINE					
STA 443+36.78 TO STA 487+61.92		4,425.14		4,425.14	1,843.81
SB I-55 OUTSIDE EDGE LINE					
STA 443+36.78 TO STA 507+61.92	6,425.14			6,425.14	2,677.14
STAGE 2					
NB I-55 MEDIAN EDGE LINE					
STA 443+27.15 TO STA 485+00.00	4,172.85			4,172.85	1,738.69
NB I-55 OUTSIDE EDGE LINE					
STA 423+27.15 TO STA 482+88.90	5,961.75			5,961.75	2,484.06
STA 482+88.90 TO STA 483+89.60			26.00	26.00	10.83
STA 483+89.60 TO STA 485+00.00	110.40			110.40	46.00
RAMP C					
STA 3+84.75 TO STA 7+60.60	375.85			375.85	156.60
STA 4+85.30 TO STA 7+60.60		275.30		275.30	114.71
SB I-55 MEDIAN EDGE LINE					
STA 447+25.53 TO STA 497+00.00		4,974.47		4,974.47	2,072.70
SB I-55 OUTSIDE EDGE LINE					
STA 447+25.53 TO STA 482+20.40	3,494.87			3,494.87	1,456.20
STA 482+20.40 TO STA 484+07.50			48.00	48.00	20.00
STA 484+07.50 TO STA 487+00.00	292.50			292.50	121.88
RAMP B					
STA 8+00.00 TO STA 11+05.30	305.30			305.30	127.21
STA 8+00.00 TO STA 9+18.45		118.45		118.45	49.35

CONTINUES NEXT SHEET



JOB = 2236.10
 FILE NAME = D672E11-sh1-Schedules.dgn
 PLOT SCALE = 1/8333 "/>

DESIGNED - NAK
 DRAWN - SJS
 CHECKED - NAK
 DATE - 1/4/12

REVISED -
 REVISED -
 REVISED -
 REVISED -

**STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION**

SCHEDULES OF QUANTITIES

SCALE: SHEET NO. 16 OF 19 SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55	D6 LOGAN CO BR 2011-1	LOGAN	429	59
CONTRACT NO. 72E11				
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				