

PAVEMENT MARKING

LOCATION	MODIFIED URETHANE PAVEMENT MARKING						SHORT-TERM PAVEMENT MARKING				WORK ZONE PAVEMENT MARKING REMOVAL SQ FT	
	5" SOLID WHITE	5" SKIP DASH	5" SOLID YELLOW	5" TOTAL	6" DOTTED	8" SOLID WHITE	MEDIAN SHOULDER	SKIP DASH	OUTSIDE SHOULDER	SHORT-TERM TOTAL		
	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT		
SN 054-0057, 054-0058												
FINAL PHASE												
NB I-55												
STA 553+35.00 TO STA 581+64.36	2,829.36	710.00	2,829.36	6,368.72			116.00	284.00	116.00	516.00	172.00	
SB I-55												
STA 572+04.50 TO STA 597+14.00	2,509.50	630.00	2,509.50	5,649.00			104.00	252.00	104.00	460.00	153.33	
SN 054-0060, 054-0061												
FINAL PHASE												
NB I-55												
STA 677+08.20 TO STA 705+83.85		720.00	2,875.65	3,595.65			116.00	288.00		404.00	134.67	
STA 677+08.20 TO STA 700+12.64	2,304.44			2,304.44					96.00	96.00	32.00	
STA 700+12.64 TO STA 703+37.40					650.00							
STA 703+37.40 TO STA 705+83.85						246.45						
RAMP B												
STA 0+00.00 TO STA 6+63.35	663.35			663.35					28.00	28.00	9.33	
STA 3+24.30 TO STA 6+63.35						339.05						
SB I-55												
STA 694+27.25 TO STA 722+54.75		710.00	2,827.50	3,537.50			116.00	284.00		400.00	133.33	
STA 694+27.25 TO STA 696+95.00	267.75			267.75					12.00	12.00	4.00	
STA 696+95.00 TO STA 704+76.20					1,564.00							
STA 704+76.20 TO STA 708+03.25						327.05						
STA 708+03.25 TO STA 722+54.75	1,451.50			1,451.50					60.00	60.00	20.00	
RAMP C												
STA 9+56.65 TO STA 25+37.75	1,581.10			1,581.10					64.00	64.00	21.33	
STA 9+56.65 TO STA 14+31.25			474.60	474.60								
STA 14+31.25 TO STA 17+56.73						325.48						
SN 054-0063, 054-0064												
FINAL PHASE												
NB I-55												
STA 261+48.39 TO STA 288+20.38	2,671.99	670.00	2,671.99	6,013.98			108.00	268.00	108.00	484.00	161.33	
SB I-55												
STA 275+58.26 TO STA 303+30.27	2,772.01	700.00	2,772.01	6,244.02			112.00	280.00	112.00	504.00	168.00	
SN 054-0065, 054-0066, 054-0067, 054-0068												
FINAL PHASE												
NB I-55												
STA 422+27.15 TO STA 485+00.00		1,570.00	6,272.85	7,842.85			252.00	628.00		880.00	293.33	
STA 422+27.15 TO STA 478+74.75	5,647.60			5,647.60					228.00	228.00	76.00	
STA 478+74.75 TO STA 481+80.75					612.00							
STA 481+80.75 TO STA 485+00.00						319.25						
RAMP C												
STA 0+00.00 TO STA 5+97.90	597.90			597.90					24.00	24.00	8.00	
STA 2+77.35 TO STA 5+97.90						320.55						
SB I-55												
STA 443+36.78 TO STA 507+61.92		1,610.00	6,425.14	8,035.14			260.00	644.00	260.00	1,164.00	388.00	
STA 443+36.78 TO STA 472+94.20	2,957.42			2,957.42					120.00	120.00	40.00	
STA 472+94.20 TO STA 481+00.10					1,612.00							
STA 481+00.10 TO STA 485+06.05						405.95						
STA 485+06.05 TO STA 507+61.92	2,255.87			2,255.87					92.00	92.00	30.67	
RAMP B												
STA 8+24.90 TO STA 19+73.25	1,148.35			1,148.35					48.00	48.00	16.00	
STA 8+24.90 TO STA 12+25.65						400.75						
TOTAL	29,658.14	7,320.00	29,658.60	66,636.74	4,438.00	2,684.53	1,184.00	2,928.00	1,472.00	5,584.00	1,861.32	



JOB = 2236.10
 FILE NAME = D672E11-sht-Schedules.dgn
 PLOT SCALE = 1/8333 "/>

DESIGNED - NAK
 DRAWN - SJS
 CHECKED - NAK
 DATE - 1/4/12

REVISED -
 REVISED -
 REVISED -
 REVISED -

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

SCHEDULES OF QUANTITIES

SCALE: SHEET NO. 18 OF 19 SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55	D6 LOGAN CO BR 2011-1	LOGAN	429	61
FED. ROAD DIST. NO.			CONTRACT NO. 72E11	
ILLINOIS FED. AID PROJECT				