



FINAL PHASE WORK SHALL CONSIST OF REMOVING SHORT TERM PAVEMENT MARKINGS AND EXISTING PAVEMENT MARKINGS, PLACING MODIFIED URETHANE PAVEMENT MARKINGS, REPLACING REFLECTORS IN EXISTING RAISED REFLECTIVE PAVEMENT MARKERS, INSTALLING RAISED REFLECTIVE PAVEMENT MARKERS, DIAMOND GRINDING AND BRIDGE DECK GROOVING ON BRIDGE DECK, BRIDGE APPROACH PAVEMENTS, AND BRIDGE APPROACH PAVEMENT CONNECTORS (PCC), AND CONSTRUCTING SHOULDER RUMBLE STRIPS.

TRAFFIC CONTROL AND PROTECTION SHALL BE ACCORDING TO STANDARDS 701400, 701401, AND 701426. THE CONTRACTOR SHALL SCHEDULE HIS OPERATIONS SO THAT ALL LANES ARE OPEN TO TRAFFIC FROM FRIDAY AT 12:00 PM UNTIL MONDAY AT 6:00 AM.

LEGEND

- ① MODIFIED URETHANE PAVEMENT MARKING - LINE 5" SOLID WHITE
- ② MODIFIED URETHANE PAVEMENT MARKING - LINE 5" WHITE SKIP DASH
- ③ MODIFIED URETHANE PAVEMENT MARKING - LINE 5" SOLID YELLOW
- ④ MODIFIED URETHANE PAVEMENT MARKING - LINE 6" WHITE 2' DASH 6' SKIP
- ⑤ MODIFIED URETHANE PAVEMENT MARKING - LINE 8" SOLID WHITE



JOB = 2265.10	DESIGNED - NAK	REVISED -
FILE NAME = D672E11-sh1-S3-5758.dgn	DRAWN - SJS	REVISED -
PLOT SCALE = 100.0000' / IN.	CHECKED - NAK	REVISED -
PLOT DATE = 3/18/2013	DATE - 3/3/2011	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**FINAL PHASE
SN 054-0057 & SN 054-0058**

SCALE: SHEET NO. 1 OF 3 SHEETS STA. 552+50 TO STA. 567+50

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55	D6 LOGAN CO BR 2011-1	LOGAN	429	111
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT			CONTRACT NO. 72E11	