

### STANDARD BAR SPLICER ASSEMBLY

Minimum Lap Lengths						
Bar size to be spliced	Table 1	Table 2	Table 3	Table 4	Table 5	Table 6
3, 4	1'-5''	1'-11''	2'-1''	2'-4''	2'-7''	2'-11''
5	1'-9''	2'-5"	2'-7''	2'-11''	3'-3''	3′-8′′
6	2'-1''	2'-11''	3'-1''	3′-6′′	3′-10′′	4′-5′′
7	2'-9''	3′-10′′	4'-2"	4'-8''	5′-2′′	5′-10′′
8	3′-8′′	5′-1′′	5′-5′′	6'-2''	6′-9′′	7′-8′′
9	4'-7''	6′-5′′	6′-10′′	7′-9′′	8'-7''	9′-8′′

Table 1: Black bar, 0.8 Class C

Table 2: Black bar, Top bar lap, 0.8 Class C

Table 3: Epoxy bar, 0.8 Class C

Table 4: Epoxy bar, Top bar lap, 0.8 Class C


Table 5: Epoxy bar, Class C

Table 6: Epoxy bar, Top bar top, Class C

Threaded splicer bar length = min. lap length +  $1^{l_2}$ " + thread length

\* Epoxy not required on Bar Splicer Assembly components used in conjunction with black bars.


Location	Bar size	No. assemblies required	Table for minimum lap length
			Tup Terrigiti
Deck, Top	#5	644	3
Deck, Bottom	#5	394	3
Approach, Top	#4	100	3
Approach, Bottom	#5	184	3
Approach, Footing	#5	80	3
Abutment, Diaphragm	#6	32	3
Abutment, Backwall	#5	8	3



## INSTALLATION AND SETTING METHODS


"A": Set bar splicer assembly by means of a template bolt.
"B": Set bar splicer assembly by nailing to wood forms or cementing to steel forms.

(E): Indicates epoxy coating.



#### STANDARD MECHANICAL SPLICER

	Bar	No. assemblies
Location	size	required
		,



#### SPECIAL BAR SPLICER ASSEMBLY

Location	Bar size	No. assemblies required	Table for minimum lap length
Diaphragm	#6	16	3

# <u>NOTES</u>

Splicer bars shall be deformed with threaded ends and have a minimum 60 ksi yield strength.

All reinforcement shall be lapped and tied to the splicer bars.

Bar splicer assemblies shall be epoxy coated according to the requirements for reinforcement bars. See Section 508 of the Standard Specifications. See approved list of bar splicer assemblies and mechanical splicers for alternatives.

BSD-1

8-31-12

Cummins	JOB = 2276.3	DESIGNED - AAN	REVISED -
	FILE = 0540057_0058-Splicer.dgn	CHECKED - MDC	REVISED -
Corporation	DATE = 2/11/2013	DRAWN - SJS	REVISED -
Civil and Structural Engineering		CHECKED - MDC	REVISED -