

STANDARD BAR SPLICER ASSEMBLY

	Minimum Lap Lengths						
Bar size to be spliced	Table 1	Table 2	Table 3	Table 4	Table 5	Table 6	
3, 4	1'-5''	1'-11''	2'-1''	2'-4''	2'-7''	2'-11''	
5	1'-9''	2'-5"	2'-7''	2'-11''	3'-3''	3′-8′′	
6	2'-1''	2'-11''	3'-1''	3'-6''	3'-10''	4'-5"	
7	2'-9''	3′-10′′	4'-2''	4'-8''	5′-2′′	5′-10′′	
8	3′-8′′	5′-1′′	5′-5′′	6'-2"	6′-9′′	7′-8′′	
9	4'-7''	6′-5′′	6′-10′′	7′-9′′	8'-7''	9′-8′′	

Table 1: Black bar, 0.8 Class C

Table 2: Black bar, Top bar lap, 0.8 Class C

Table 3: Epoxy bar, 0.8 Class C

Table 4: Epoxy bar, Top bar lap, 0.8 Class C


Table 5: Epoxy bar, Class C

Table 6: Epoxy bar, Top bar top, Class C

Threaded splicer bar length = min. lap length + 1_2^{l} " + thread length

* Epoxy not required on Bar Splicer Assembly components used in conjunction with black bars.


	Bar	No. assemblies	Table for minimum			
Location	size	required	lap length			



INSTALLATION AND SETTING METHODS


"A": Set bar splicer assembly by means of a template bolt.
"B": Set bar splicer assembly by nailing to wood forms or cementing to steel forms.

(E): Indicates epoxy coating.




STANDARD MECHANICAL SPLICER

Location	Bar size	No. assemblies required



BAR SPLICER ASSEMBLY FOR #5 BAR ON INTEGRAL OR SEMI-INTEGRAL ABUTMENTS

No. required = 176



<u>NOTES</u>

Splicer bars shall be deformed with threaded ends and have a minimum 60 ksi yield strength.

All reinforcement shall be lapped and tied to the splicer bars.

Bar splicer assemblies shall be epoxy coated according to the requirements for reinforcement bars. See Section 508 of the Standard Specifications. See approved list of bar splicer assemblies and mechanical splicers for

alternatives.

Coombe-Bloxdorf P.C.
-civil Engineers-structural Engineers-LAND SURVEYORSDesign Firm License No. 184-002703

BSD-1

1-27-12

FILE NAME =	USER NAME = _MML_	DESIGNED -	-	GJB	REVISED	-	
\0540065-0066-72ell-038-bar-splicers.dgn			-	MCB/RKM	REVISED	-	
	PLOT SCALE = 0:2.0000000 ':" / IN.	DRAWN -	-	CFC	REVISED	-	
CB PROJECT NO. 10065-1	PLOT DATE = 3/18/2013	CHECKED -	-	MCB/GJB	REVISED	-	

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

BAR SPLICER ASSEMBLY AND MECHANICAL SPLICER DETAILS STRUCTURE NO. 054-0065 (N.B.) & 054-0066 (S.B.)

SHEET NO. 38 OF 39 SHEETS