

80% FED
20% STATE

80% FED
20% STATE

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		0005	0014	
20200600	EXCAVATING AND GRADING EXISTING SHOULDER	UNIT	982	982		
35600716	HOT-MIX ASPHALT BASE COURSE WIDENING, 10"	SO YD	362	362		
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	238	238		
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	15793	15793		
40600300	AGGREGATE (PRIME COAT)	TON	316	316		
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	5821	5821		
40600645	LEVELING BINDER (MACHINE METHOD), N90	TON	812	812		
40600895	CONSTRUCTING TEST STRIP	EACH	1	1		
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	941	941		
40600990	TEMPORARY RAMP	SO YD	179	179		
40603315	HOT-MIX ASPHALT SURFACE COURSE, "C", N70	MIX TON	12807	12807		
40603545	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N90	TON	1762	1762		

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		0005	0014	
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	137	137		
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SO YD	19972	19972		
44201827	CLASS D PATCHES, TYPE II, 15 INCH	SO YD	2947	2947		
44201831	CLASS D PATCHES, TYPE III, 15 INCH	SO YD	1024	1024		
44201833	CLASS D PATCHES, TYPE IV, 15 INCH	SO YD	1301	1301		
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	2783	2783		
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SO YD	215	215		
50102400	CONCRETE REMOVAL	CU YD	12.4		12.4	
50300255	CONCRETE SUPERSTRUCTURE	CU YD	12.4		12.4	
50300300	PROTECTIVE COAT	SO YD	30		30	
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	2080		2080	
50800515	BAR SPLICERS	EACH	12		12	
52000110	PREFORMED JOINT STRIP SEAL	FOOT	44		44	
66700205	PERMANENT SURVEY MARKERS, TYPE I	EACH	24		24	

FILE NAME :	USER NAME : staffanek	DESIGNED -	REVISED -
e:\p\work\p\p\dat\staffanek\d0147948\07	440R-shl-800.dgn	DRAWN -	REVISED -
	PLOT SCALE = 100.0000' / in.	CHECKED -	REVISED -
	PLOT DATE = 3/18/2013	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: NA	SHEET NO. 1 OF 3 SHEETS	STA.	TO STA.	F.A.P. RTE. 116	SECTION (124,125,126)RS-3	COUNTY RICHLAND	TOTAL SHEETS 60	SHEET NO. 4
CONTRACT NO. 74409								ILLINOIS FED. AID PROJECT