

PAVEMENT MARKING SCHEDULE

PAVEMENT MARKING SCHEDULE (Cont' d)			LENGTH	SHORT-TERM PAVEMENT MARKING	TEMPORARY PAVEMENT MARKING- LETTER AND SYMBOLS	TEMPORARY PAVEMENT MARKING-LINE 4"	TEMPORARY PAVEMENT MARKING-LINE 4" (YELLOW SKIP-DASH)	TEMPORARY PAVEMENT MARKING-LINE 4" (WHITE)	TEMPORARY PAVEMENT MARKING-LINE 6"	TEMPORARY PAVEMENT MARKING-LINE 12"	TEMPORARY PAVEMENT MARKING-LINE 24"	WORK ZONE PAVEMENT MARKING REMOVAL	PAINT PAVEMENT MARKING-LINE 4" (YELLOW)	PAINT PAVEMENT MARKING-LINE 4" (YELLOW SKIP-DASH)	PAINT PAVEMENT MARKING-LINE 4" (WHITE)	THERMOPLASTIC PAVEMENT MARKING-LETTERS & SYMBOLS	THERMOPLASTIC PAVEMENT MARKING-LINE 4" (YELLOW)	THERMOPLASTIC PAVEMENT MARKING-LINE 4" (YELLOW SKIP-DASH)	THERMOPLASTIC PAVEMENT MARKING-LINE 4" (WHITE)	THERMOPLASTIC PAVEMENT MARKING-LINE 6"	THERMOPLASTIC PAVEMENT MARKING-LINE 12"	THERMOPLASTIC PAVEMENT MARKING-LINE 24"	RAISED REFLECTIVE PAVEMENT MARKER, MONO-DIRECTIONAL (CRYSTAL)	RAISED REFLECTIVE PAVEMENT MARKER, MONO-DIRECTIONAL (AMBER)	RAISED REFLECTIVE PAVEMENT MARKER, BI-DIRECTIONAL (AMBER)
STATION	TO	STATION	FOOT	FOOT	SO FT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	SO FT	FOOT	FOOT	FOOT	SO FT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	EACH	EACH	EACH
311+65.00	TO	318+38.00	673.0	269.2	0.0	673.0	168.3	1,346.0	0.0	0.0	0.0	751.7	673.0	168.3	1,346.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0	0	8
318+38.00	TO	321+61.00	323.0	129.2	0.0	0.0	80.8	646.0	0.0	0.0	0.0	253.1	0.0	80.8	646.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0	0	4
321+61.00	TO	322+87.00	126.0	50.4	0.0	126.0	31.5	252.0	0.0	0.0	0.0	140.7	126.0	31.5	252.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0	0	2
322+87.00	TO	334+99.00	1,212.0	484.8	0.0	2,424.0	0.0	2,260.0	0.0	0.0	0.0	1,602.1	2,424.0	0.0	2,260.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0	0	30
334+99.00	TO	344+93.00	994.0	397.6	0.0	994.0	248.5	1,988.0	0.0	0.0	0.0	1,110.2	994.0	248.5	1,988.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0	0	12
344+93.00	TO	470+16.09	12,523.1	5,009.2	0.0	0.0	3,130.8	24,750.2	0.0	0.0	0.0	9,713.0	0.0	3,130.8	24,750.2	0.0	0.0	0.0	0.0	0.0	0.0	0.0	48	0	170
470+16.09	=	470+71.10AH																							
470+71.10	TO	509+10.40	3,839.3	1,535.7	0.0	0.0	959.8	7,574.6	0.0	0.0	0.0	2,973.4	0.0	959.8	7,574.6	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0	0	48
509+10.40	=	509+10.90AH																							
509+10.90	TO	534+50.00	2,539.1	1,015.6	0.0	0.0	634.8	5,078.2	0.0	0.0	0.0	1,989.4	0.0	634.8	5,078.2	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0	0	32
534+50.00	TO	535+97.00	147.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0	0	0
535+97.00	TO	538+40.99	244.0	97.6	0.0	0.0	61.0	488.0	0.0	0.0	0.0	191.2	0.0	61.0	488.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0	0	3
538+40.99	TO	546+47.99	807.0	322.8	0.0	807.0	201.8	1,521.0	0.0	0.0	0.0	870.3	807.0	201.8	1,521.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0	0	10
546+47.99	TO	547+95.99	148.0	59.2	0.0	0.0	37.0	296.0	0.0	0.0	0.0	116.0	0.0	37.0	296.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0	0	2
547+95.99	TO	557+93.99	998.0	399.2	0.0	998.0	249.5	1,843.0	0.0	0.0	0.0	1,063.6	998.0	249.5	1,843.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0	0	12
557+93.99	TO	572+25.97	1,432.0	572.8	0.0	0.0	358.0	2,783.0	0.0	0.0	0.0	1,094.9	0.0	358.0	2,783.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	46	0	31
572+25.97	=	572+85.70AH																							
572+85.70	TO	580+09.72	724.0	289.6	0.0	0.0	181.0	1,372.0	0.0	0.0	0.0	541.9	0.0	181.0	1,372.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0	0	9
580+09.72	TO	588+24.72	815.0	326.0	0.0	815.0	203.8	1,630.0	0.0	0.0	0.0	910.3	815.0	203.8	1,630.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0	0	10
588+24.72	TO	590+79.72	255.0	102.0	0.0	0.0	63.8	510.0	0.0	0.0	0.0	199.8	0.0	63.8	510.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0	0	3
590+79.72	TO	599+30.72	851.0	340.0	0.0	851.0	212.8	1,649.0	0.0	0.0	0.0	932.8	851.0	212.8	1,649.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0	0	11
599+30.72	TO	605+05.78	575.1	230.0	0.0	0.0	143.8	1,150.1	0.0	0.0	0.0	450.6	0.0	143.8	1,150.1	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0	0	7
605+05.78	=	605+07.60AH																							
605+07.60	TO	630+90.00	2,582.4	1,033.0	0.0	0.0	645.6	5,164.8	0.0	0.0	0.0	2,023.3	0.0	645.6	5,164.8	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0	0	32
630+90.00	TO	632+22.92	132.9	53.2	0.0	132.9	33.2	265.8	0.0	0.0	0.0	148.5	132.9	33.2	265.8	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0	0	2
SHEET TOTALS			31,941	12,717	0	7,821	7,645	62,568	0	0	0	27,077	7,821	7,645	62,568	0	0	0	0	0	0	0	94	0	439
PROJECT TOTALS			57,016.5	22,628	94	29,171	12,240	108,809	287	554	32	52,852	15,182	11,954	99,385	94	13,989	287	10,424	287	554	32	103	81	793