

80% FED.
20% STATE

80% FED.
20% STATE

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		0004	0021	
X5400504	PRECAST CONCRETE BOX CULVERTS 2' X 2' (SPECIAL)	FOOT	72	72		
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	622	622		
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	354	354		
20200100	EARTH EXCAVATION	CU YD	5428	5428		
*25000200	SEEDING, CLASS 2	ACRE	1.7	1.7		
*25000400	NITROGEN FERTILIZER NUTRIENT	POUND	146	146		
*25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	146	146		
*25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	146	146		
*25000700	AGRICULTURAL GROUND LIMESTONE	TON	3	3		
*25100115	MULCH, METHOD 2	ACRE	1.7	1.7		
*28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	162	162		
28000305	TEMPORARY DITCH CHECKS	FOOT	160	160		
28000500	INLET AND PIPE PROTECTION	EACH	6	6		

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		0004	0021	
28100105	STONE RIPRAP, CLASS A3	SQ YD	24	24		
28200200	FILTER FABRIC	SQ YD	24	24		
31101000	SUBBASE GRANULAR MATERIAL, TYPE B	TON	1997	1997		
35101400	AGGREGATE BASE COURSE, TYPE B	TON	44	44		
35501316	HOT-MIX ASPHALT BASE COURSE, 8"	SQ YD	210	210		
35600714	HOT-MIX ASPHALT BASE COURSE WIDENING, 9 1/2"	SQ YD	2943	2943		
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	48	48		
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	1504	1504		
40600300	AGGREGATE (PRIME COAT)	TON	19	19		
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	285	285		
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	292	292		
40600990	TEMPORARY RAMP	SQ YD	66	66		
40603315	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N70	TON	793	793		
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	30	30		

*SPECIALTY ITEM

FILE NAME :	USER NAME : stoffenmk	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
c:\pwork\pudat\stoeffenmk\030911147	4567.sht-saa.dgn	DRAWN -	REVISED -			116	126N	EDWARDS	71	4	
Default	PLOT SCALE = 100.0000 1 / in	CHECKED -	REVISED -			CONTRACT NO. 74567					
	PLOT DATE = 3/18/2013	DATE -	REVISED -			ILLINOIS FED. AID PROJECT					

27