

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		0014		
35300500	PORTLAND CEMENT CONCRETE BASE COURSE 10"	SO YD	931	931		
35400500	PORTLAND CEMENT CONCRETE BASE COURSE WIDENING 10"	SO YD	658	658		
40600990	TEMPORARY RAMP	SO YD	107	107		
40603345	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N90	TON	15	15		
42001200	PAVEMENT FABRIC	SO YD	1589	1589		
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SO YD	172	172		
44004250	PAVED SHOULDER REMOVAL	SO YD	1589	1589		
50102400	CONCRETE REMOVAL	CU YD	28	28		
50300100	FLOOR DRAINS	EACH	32	32		
50300255	CONCRETE SUPERSTRUCTURE	CU YD	28	28		
50300260	BRIDGE DECK GROOVING	SO YD	916	916		
50300300	PROTECTIVE COAT	SO YD	78	78		
50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	3020	3020		

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		0014		
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	3920	3920		
50800515	BAR SPLICERS	EACH	56	56		
52000110	PREFORMED JOINT STRIP SEAL	FOOT	174	174		
52100010	ELASTOMERIC BEARING ASSEMBLY, TYPE I	EACH	14	14		
52100020	ELASTOMERIC BEARING ASSEMBLY, TYPE II	EACH	14	14		
52100520	ANCHOR BOLTS, 1"	EACH	56	56		
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	11	11		
67100100	MOBILIZATION	L SUM	1	1		
70100320	TRAFFIC CONTROL AND PROTECTION, STANDARD 701422	L SUM	1	1		
70100325	TRAFFIC CONTROL AND PROTECTION, STANDARD 701423	EACH	2	2		
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1		
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	12	12		

FILE NAME :	USER NAME : staffanmk	DESIGNED -	REVISED -
c:\pwworkspace\staffanmk\140312827\07	74600-shs-400.dgn	DRAWN -	REVISED -
Default	PLOT SCALE = 100.0000 / 1 in.	CHECKED -	REVISED -
	PLOT DATE = 3/29/2013	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: N/A SHEET 1 OF 2 SHEETS STA. TO STA.

* 07 Bridge Repairs 2014-1				
F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
327	*	CLAY	49	3
CONTRACT NO. 74600			ILLINOIS FED. AID PROJECT	