

# LOCATION 9

## I-57 & 1000 N/E CO RD 1000N - COLES COUNTY

## USE DETAIL "A"

### SIGNS

SIGN TYPES BY LOCATION	UNITS	NB EXIT RAMP	SB EXIT RAMP
FREEWAY ENTRANCE (D13-3) 48" x 30"	EACH	0	0
DIRECTIONAL ARROW (M6-2a) 21" x 15"	EACH	0	0
STOP SIGN (R1-1) 48" x 48"	EACH	3	3
NO RIGHT TURN (R3-1) 36" x 36"	EACH	1	1
NO LEFT TURN (R3-2) 36" x 36"	EACH	2	2
KEEP RIGHT (R4-7) 40" x 60"	EACH	0	0
DO NOT ENTER (R5-1) 36" x 36"	EACH	1	1
DO NOT ENTER (R5-1) 48" x 48"	EACH	2	2
WRONG WAY (R5-1a) 42" x 30"	EACH	4	4
ONE WAY (R6-1 - LEFT) 54" x 18"	EACH	3	3
ONE WAY (R6-1 - RIGHT) 54" x 18"	EACH	3	3
RETROREFLECTIVE SIGN SUPPORT PANEL (RED) 2" x 60"	EACH	7	7
CHEVRON (W1-8 - YELLOW) 30" x 36"	EACH	10	9

### BILL OF MATERIALS

PAY ITEM DESCRIPTION	UNITS	NB EXIT RAMP	SB EXIT RAMP
SIGN PANEL - TYPE 1	SQ FT	172.1	164.6
SIGN PANEL - TYPE 2	SQ FT	80.0	80.0
REMOVE SIGN PANEL - TYPE 1	SQ FT	50.5	50.5
REMOVE SIGN PANEL - TYPE 2	SQ FT	32.0	32.0
RELOCATE SIGN PANEL - TYPE 1	SQ FT	0.0	0.0
RELOCATE SIGN PANEL - TYPE 2	SQ FT	0.0	0.0
WOOD SIGN SUPPORT	FOOT	308.0	295.0
REMOVE GROUND MOUNTED SIGN SUPPORT	EACH	7.0	7.0
THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	0.0	0.0
THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	0.0	0.0
THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	0.0	0.0
THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	0.0	0.0
THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	0.0	0.0
MODIFIED URETHANE PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	55.5	55.5
MODIFIED URETHANE PAVEMENT MARKING - LINE 4"	FOOT	0.0	0.0
MODIFIED URETHANE PAVEMENT MARKING - LINE 8"	FOOT	150.0	150.0
MODIFIED URETHANE PAVEMENT MARKING - LINE 12"	FOOT	50.0	50.0
MODIFIED URETHANE PAVEMENT MARKING - LINE 24"	FOOT	40.0	40.0
PAVEMENT MARKING REMOVAL	SQ FT	100.0	100.0
WOOD SIGN SUPPORT, SPECIAL	FOOT	15.0	15.0

FILE NAME =	USER NAME = steffenmk	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>BILL OF MATERIALS LOCATION 9</b>			F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.			
ct:\pw\work\p\dot\steffenmk\d0339033\0774614-Int_Signs.dgn		DRAWN -	REVISED -								44	13			
Default	PLOT SCALE = 40.0000' / in.	CHECKED -	REVISED -					SCALE:	SHEET	OF	SHEETS	STA.	TO	STA.	CONTRACT NO. 74614
	PLOT DATE = 3/28/2013	DATE -	REVISED -												ILLINOIS FED. AID PROJECT