

TEMPORARY CONCRETE BARRIER			
STAGE	LOCATION	WORK AREA	FOOT
STAGE I	RT. STA. 542+25 TO RT. STA. 553+50	S.B. P.L.	1,125
STAGE I	RT. STA. 636+25 TO RT. STA. 648+50	S.B. P.L.	1,225
STAGE III	LT. STA. 547+50 TO LT. STA. 558+75	N.B. P.L.	1,125
STAGE III	LT. STA. 640+00 TO LT. STA. 652+75	N.B. P.L.	1,275
TOTAL =			4,750

RELOCATE TEMPORARY CONCRETE BARRIER			
STAGE	LOCATION	WORK AREA	FOOT
STAGE II	RT. STA. 542+25 TO RT. STA. 553+50	S.B. D.L.	1,125
STAGE II	RT. STA. 636+25 TO RT. STA. 648+50	S.B. D.L.	1,225
STAGE IV	LT. STA. 547+50 TO LT. STA. 558+75	N.B. D.L.	1,125
STAGE IV	LT. STA. 640+00 TO LT. STA. 652+75	N.B. D.L.	1,275
TOTAL =			4,750

BARRIER WALL MARKERS, TYPE C			
STAGE	LOCATION	WORK AREA	EACH
STAGE I	RT. STA. 544+05 TO RT. STA. 553+55	S.B. P.L.	76
STAGE I	RT. STA. 638+05 TO RT. STA. 648+55	S.B. P.L.	84
STAGE III	LT. STA. 545+55 TO LT. STA. 555+05	N.B. P.L.	76
STAGE III	LT. STA. 638+05 TO LT. STA. 649+05	N.B. P.L.	88
TOTAL =			324

SIGN PANEL - TYPE 1 TELESCOPING STEEL SIGN SUPPORT		
LOCATION	SIGN PANEL - TYPE 1 (SQ. FT.)	SIGN SUPPORT (FOOT)
IL 4 RAMPS - "NO PARKING" SIGNS		
RAMP 1		
STA. 103+00	5	12
STA. 106+00	5	12
STA. 109+00	5	12
STA. 112+00	5	12
STA. 115+00	5	12
RAMP 2		
STA. 206+00	5	12
STA. 209+00	5	12
STA. 212+00	5	12
RAMP 3		
STA. 302+50	5	12
STA. 305+50	5	12
STA. 308+50	5	12
STA. 311+50	5	12
STA. 314+50	5	12
RAMP 4		
STA. 406+00	5	12
STA. 409+00	5	12
STA. 412+00	5	12
TOTAL =		
	80	192

PAINT PAVEMENT MARKING - LINE 4''		
LOCATION	COLOR	FOOT
PRE-STAGE (REPLACE STRIPING DURING PIPE UNDERDRAIN INSTALLATION)		
I-55		
SB D.L. STA. 519+00 TO STA. 532+50	WHITE	1350
SB D.L. STA. 535+30 TO STA. 560+90	WHITE	2560
SB D.L. STA. 567+40 TO STA. 670+00	WHITE	10260
SB P.L. STA. 519+00 TO STA. 670+00	YELLOW	15100
NB P.L. STA. 519+00 TO STA. 670+00		
NB D.L. STA. 519+00 TO STA. 532+80	YELLOW	15100
NB D.L. STA. 539+00 TO STA. 566+40	WHITE	1380
NB D.L. STA. 569+00 TO STA. 670+00	WHITE	2740
NB D.L. STA. 569+00 TO STA. 670+00	WHITE	10100
IL 4 INTERCHANGE		
RAMP 1 LT. STA. 100+70 TO LT. STA. 113+00	YELLOW	1230
STA. 100+30 TO STA. 124+60	WHITE	2430
RAMP 2 STA. 200+00 TO STA. 214+00		
LT. STA. 207+00 TO LT. STA. 214+30	WHITE	1400
	YELLOW	730
RAMP 3 LT. STA. 300+50 TO LT. STA. 312+70		
STA. 300+30 TO STA. 324+50	YELLOW	1220
	WHITE	2420
RAMP 4 STA. 400+15 TO STA. 413+50		
LT. STA. 407+00 TO LT. STA. 413+80	WHITE	1335
	YELLOW	680
SUBTOTAL =		
		70,035
TO BE USED TO MARK LANES DURING STAGING WORK.		
	WHITE - FOOT	YELLOW - FOOT
STAGE I		
SB D.L. STA. 519+00 TO STA. 670+00	15100	15100
OMIT RAMP 4 GAP STA. 532+50 TO STA. 535+50	-300	
OMIT RAMP 3 GAP STA. 561+00 TO STA. 567+50	-650	
SUBTOTAL STAGE I		
	14150	15100
STAGE II		
SB P.L. STA. 519+00 TO STA. 670+00	15100	15100
SUBTOTAL STAGE II		
	15100	15100
STAGE III		
NB D.L. STA. 519+00 TO STA. 670+00	15100	15100
OMIT RAMP 1 GAP STA. 532+80 TO STA. 539+00	-620	
OMIT RAMP 2 GAP STA. 566+50 TO STA. 569+20	-270	
SUBTOTAL STAGE III		
	14210	15100
STAGE IV		
NB P.L. STA. 519+00 TO STA. 670+00	15100	15100
SUBTOTAL STAGE IV		
	15100	15100
TOTAL =		
		188,995

PAVEMENT MARKING REMOVAL		
LOCATION	WHITE (SQ. FT.)	YELLOW (SQ. FT.)
SB D.L. STAGE I STA. 519+00 TO STA. 670+00	4717	---
SB P.L. STAGE II STA. 519+00 TO STA. 670+00 (UPON COMPLETION OF STAGE II)	5033	5033
NB D.L. STAGE III STA. 519+00 TO STA. 670+00	4737	---
NB P.L. STAGE IV STA. 519+00 TO STA. 670+00 (UPON COMPLETION OF STAGE IV)	5033	5033
TOTAL =		
	29,586	

GREENBOARD SIGN REMOVAL QUANTITIES

REMOVE SIGN PANEL ASSEMBLY - TYPE B REMOVE SIGN PANEL - TYPE 2 REMOVE SIGN PANEL - TYPE 3 REMOVE GROUND MOUNTED SIGN SUPPORT REMOVE CONCRETE FOUNDATION - GROUND MOUNT					
LOCATION	SIGN ASSEM. TYPE B (EACH)	SIGN PANEL TYPE 2 (SQ. FT.)	SIGN PANEL TYPE 3 (SQ. FT.)	GRND. MNTD. SIGN SUPP. (EACH)	CONC. FND. GRND. MNTD. (EACH)
MAINLINE STATIONS					
SB STA. 290+12, 107' RT.	1	17	153	2	2
SB STA. 316+54, 106' RT.	1	17	136	2	2
NB STA. 326+58, 107' LT.	-	-	127.5	2	2
SB STA. 342+69, 106' RT.	1	17	170	2	2
SB STA. 355+60, GORE	-	-	30	2	-
RAMP STA. 358+46, 544' LT.	-	-	172.5	2	2
RAMP STA. 360+38, 490' LT.	-	-	81	2	2
RAMP STA. 362+97, 755' RT.	-	-	74.75	2	2
RAMP STA. 364+14, 736' LT.	-	-	74.75	2	2
RAMP STA. 366+34, 518' RT.	-	-	96	2	2
NB STA. 367+04, GORE	-	-	30	2	-
RAMP STA. 368+19, 548' RT.	-	-	201.25	2	2
NB STA. 381+00, 106' LT.	1	18	170	2	2
SB STA. 400+24, 108' RT.	-	-	142.5	2	2
NB STA. 404+13, 106' LT.	1	18	136	2	2
NB STA. 433+83, 104' LT.	1	18	153	2	2
SB STA. 479+98, 106' RT.	1	18	156.25	2	2
SB STA. 490+13, 101 RT.	-	-	45	2	2
SB STA. 517+91, 80' RT.	1	18	150	2	2
SB STA. 532+34, 82 RT.	1	18	156.25	2	2
SB STA. 539+16, GORE	-	-	30	2	-
RAMP STA. 542+75, 259' RT.	-	-	40.5	2	2
RAMP STA. 544+65, 580' RT.	-	-	159.5	2	2
RAMP STA. 545+28, 375' RT.	-	-	79.75	2	2
RAMP STA. 555+53, 365' LT.	-	-	68.75	2	2
RAMP STA. 556+31, 560' LT.	-	-	159.5	2	2
RAMP STA. 557+91, 306' LT.	-	-	40.5	2	2
NB STA. 562+14, GORE	-	-	30	2	-
NB STA. 569+17, 82' LT.	1	18	156.25	2	2
NB STA. 589+00, 80' LT.	1	18	150	2	2
NB STA. 608+00, 77' LT.	1	18	156.25	2	2
NB STA. 617+00, 81' LT.	-	-	45	2	2
TOTAL =					
	12	213	3571.75	64	56