

RAISED REFLECTIVE PAVEMENT MARKER	
LOCATION	EACH
I55	
STA. 519+00.00 TO STA. 670+00.00 (NB & SB LANES)	756
STA. 537+66.07 TO STA. 539+68.00 (WHITE EDGELINE) RT	5
STA. 542+15.33 TO STA. 544+42.25 (WHITE EDGELINE) LT	6
STA. 555+69.64 TO STA. 557+97.25 (WHITE EDGELINE) RT	6
STA. 562+04.57 TO STA. 563+84.59 (WHITE EDGELINE) LT	5
IL 4 RAMPS	
RAMP 1	
STA. 112+56.16 TO STA. 115+28.59 (WHITE EDGELINE) LT	7
RAMP 2	
STA. 205+32.07 TO STA. 207+11.25 (WHITE EDGELINE) LT	4
STA. 200+00.21 TO STA. 207+11.25 (WHITE EDGELINE) RT	36
RAMP 3	
STA. 312+29.68 TO STA. 315+03.56 (WHITE EDGELINE) LT	7
RAMP 4	
STA. 405+30.92 TO STA. 407+32.69 (WHITE EDGELINE) LT	5
STA. 400+13.09 TO STA. 407+32.69 (WHITE EDGELINE) RT	36
TOTAL =	873

RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	
LOCATION	EACH
I55	
STA. 519+00.00 TO STA. 670+00.00 (NB & SB LANES)	756
STA. 537+66.07 TO STA. 539+68.00 (WHITE EDGELINE) RT	5
STA. 542+15.33 TO STA. 544+42.25 (WHITE EDGELINE) LT	6
STA. 555+69.64 TO STA. 557+97.25 (WHITE EDGELINE) RT	6
STA. 562+04.57 TO STA. 563+84.59 (WHITE EDGELINE) LT	5
IL 4 RAMPS	
RAMP 1	
STA. 112+56.16 TO STA. 115+28.59 (WHITE EDGELINE) LT	7
RAMP 2	
STA. 205+32.07 TO STA. 207+11.25 (WHITE EDGELINE) LT	4
STA. 200+00.21 TO STA. 207+11.25 (WHITE EDGELINE) RT	36
RAMP 3	
STA. 312+29.68 TO STA. 315+03.56 (WHITE EDGELINE) LT	7
RAMP 4	
STA. 405+30.92 TO STA. 407+32.69 (WHITE EDGELINE) LT	5
STA. 400+13.09 TO STA. 407+32.69 (WHITE EDGELINE) RT	36
TOTAL =	873

HIGH TENSION CABLE MEDIAN BARRIER DEMONSTRATION	
LOCATION	EACH
SECTION 60-(1,2)RS-3	1
TOTAL =	1

HIGH TENSION CABLE MEDIAN BARRIER	
LOCATION	FOOT
RT. STA. 519+50 TO RT. STA. 565+95	4,645
LT. STA. 566+45 TO LT. STA. 604+00	3,755
LT. STA. 604+50 TO LT. STA. 642+50	3,800
RT. STA. 645+00 TO RT. STA. 609+50	2,450
TOTAL =	14,650

HIGH TENSION CABLE MEDIAN BARRIER TERMINALS	
LOCATION	EACH
RT. STA. 519+00 TO RT. STA. 519+50	2
RT. STA. 565+95 TO RT. STA. 566+45	1
LT. STA. 565+95 TO LT. STA. 566+45	1
LT. STA. 604+00 TO LT. STA. 604+50	2
LT. STA. 642+50 TO LT. STA. 643+00	1
RT. STA. 644+50 TO RT. STA. 645+00	1
RT. STA. 669+50 TO RT. STA. 670+00	2
TOTAL =	10

WEED CONTROL MOWING STRIP (SPECIAL)	
LOCATION	SQ YD
RT. STA. 519+00 TO RT. STA. 566+45	2109
LT. STA. 565+95 TO LT. STA. 643+00	3424
RT. STA. 644+50 TO RT. STA. 670+00	1133
TOTAL =	6,666

REMOVE HIGH TENSION CABLE MEDIAN BARRIER	
LOCATION	FOOT
RT. STA. 519+00 TO RT. STA. 565+95	4,695
LT. STA. 566+45 TO LT. STA. 642+50	7,605
RT. STA. 645+00 TO RT. STA. 668+00	2,300
RT. STA. 668+50 TO RT. STA. 670+00	150
TOTAL =	14,750

REMOVE HIGH TENSION CABLE MEDIAN BARRIER TERMINAL	
LOCATION	EACH
RT. STA. 565+95 TO RT. STA. 566+45	1
LT. STA. 565+95 TO LT. STA. 566+45	1
LT. STA. 642+50 TO LT. STA. 643+00	1
RT. STA. 644+50 TO RT. STA. 645+00	1
RT. STA. 668+00 TO RT. STA. 668+50	2
TOTAL =	6

IMPACT ATTENUATORS, RELOCATE (FULLY REDIRECTIVE), TEST LEVEL 3			
STAGE	LOCATION	WORK AREA	EACH
STAGE II	RT. STA. 542+25	S.B. D.L.	1
STAGE II	RT. STA. 636+25	S.B. D.L.	1
STAGE IV	LT. STA. 558+75	N.B. D.L.	1
STAGE IV	LT. STA. 652+75	N.B. D.L.	1
TOTAL =			4

IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3			
STAGE	LOCATION	WORK AREA	EACH
STAGE I	RT. STA. 542+25	S.B. P.L.	1
STAGE I	RT. STA. 636+25	S.B. P.L.	1
STAGE III	LT. STA. 558+75	N.B. P.L.	1
STAGE III	LT. STA. 652+75	N.B. P.L.	1
TOTAL =			4

IMPACT ATTENUATOR REMOVAL IMPACT ATTENUATORS (NON-REDIRECTIVE), TEST LEVEL 3		
LOCATION	ATTEN. REM. (EACH)	ATTEN. (N-R) TL 3 (EACH)
STA. 549+65	1	1
STA. 550+80	1	1
STA. 643+57	1	1
STA. 644+00	1	1
TOTAL =	4	4