

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTR. CODE	
				ROADWAY	RURAL
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	44.2	44.2	
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	40.2	40.2	
40600300	AGGREGATE (PRIME COAT)	TON	195	195	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	218	218	
40600990	TEMPORARY RAMP	SQ YD	114	114	
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	11271.6	11271.6	
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	233.2	233.2	
44000152	HOT-MIX ASPHALT SURFACE REMOVAL, 3/4"	SQ YD	81612	81612	
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	129	129	
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	7214	7214	
44200192	PAVEMENT PATCHING, TYPE II, 16 INCH	SQ YD	958	958	
44200196	PAVEMENT PATCHING, TYPE III, 16 INCH	SQ YD	240	240	
44200198	PAVEMENT PATCHING, TYPE IV, 16 INCH	SQ YD	197	197	
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	69790	69790	

CONSTR. CODE  
80% FED  
20% STATE

ROADWAY  
0005  
RURAL

14

FILE NAME =	USER NAME = challondeske	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>				F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
c:\pwork\pwork\challondeske\d0115523	0876288-sh-1-500.dgn	DRAWN -	REVISED -						103	(23, 24) RS-4	ST. CLAIR	54	3
#MODELNAME#	PLOT SCALE = 100.0000' / 1" in.	CHECKED -	REVISED -		SCALE: N/A SHEET 1 OF 3 SHEETS STA. TO STA.				CONTRACT NO. 76E88				
	PLOT DATE = 3/22/2013	DATE -	REVISED -		ILLINOIS FED. AID PROJECT								