

PATCHING SCHEDULE

LOCATION	DIRECTION (EB/WB/NB/SB)	WIDTH FOOT	LENGTH FOOT	AREA SQ YD	PAVEMENT PATCHING		
					TYPE II SQ YD	TYPE III SQ YD	TYPE IV SQ YD
576+70	EB	12	10	13.3	13.3		
576+70	WB	12	10	13.3	13.3		
578+30	EB	11	10	12.2	12.2		
578+30	WB	11	10	12.2	12.2		
579+90	WB	11	6	7.3	7.3		
580+25	EB	11	6	7.3	7.3		
581+10	EB	11	6	7.3	7.3		
581+10	WB	11	6	7.3	7.3		
582+70	EB	11	10	12.2	12.2		
589+60	EB	11	12	14.7	14.7		
589+60	WB	11	12	14.7	14.7		
591+60	EB	11	6	7.3	7.3		
591+60	WB	11	6	7.3	7.3		
592+60	EB	11	8	9.8	9.8		
592+60	WB	11	8	9.8	9.8		
596+70	EB	11	12	14.7	14.7		
606+10	EB	11	10	12.2	12.2		
606+10	WB	11	10	12.2	12.2		
607+20	EB	11	30	36.7			36.7
607+20	WB	11	30	36.7			36.7
613+15	EB	11	6	7.3	7.3		
613+15	WB	11	6	7.3	7.3		
614+60	EB	11	10	12.2	12.2		
614+60	WB	11	10	12.2	12.2		
621+70	EB	11	20	24.4		24.4	
621+70	WB	11	6	7.3	7.3		
625+70	WB	11	10	12.2	12.2		
625+80	EB	11	10	12.2	12.2		
632+25	EB	11	6	7.3	7.3		
632+25	WB	11	6	7.3	7.3		
632+40	WB	11	6	7.3	7.3		
638+00	EB	11	40	48.9			48.9
638+00	WB	11	40	48.9			48.9
638+90	EB	11	12	14.7	14.7		
638+90	WB	11	12	14.7	14.7		
639+20	EB	11	10	12.2	12.2		
639+20	WB	11	10	12.2	12.2		
653+00	EB	11	6	7.3	7.3		
653+00	WB	11	6	7.3	7.3		
654+00	EB	11	12	14.7	14.7		
654+00	WB	11	6	7.3	7.3		
657+40	EB	11	6	7.3	7.3		
657+40	WB	11	6	7.3	7.3		
666+70	EB	11	6	7.3	7.3		
672+00	EB	11	10	12.2	12.2		
672+00	WB	11	10	12.2	12.2		
675+00	EB	11	6	7.3	7.3		
675+00	WB	11	6	7.3	7.3		
676+60	EB	11	6	7.3	7.3		
676+60	WB	11	6	7.3	7.3		
SUBTOTAL =					454.4	24.4	171.1
ADDITIONAL 15% =					522.6	28.1	196.8
TOTAL (A) =					523	29	197

LOCATION	DIRECTION (EB/WB/NB/SB)	WIDTH FOOT	LENGTH FOOT	AREA SQ YD	PAVEMENT PATCHING		
					TYPE II SQ YD	TYPE III SQ YD	TYPE IV SQ YD
669+00	EB	11	6	7.3	7.3		
669+00	WB	11	6	7.3	7.3		
669+95	EB	11	10	12.2	12.2		
669+95	WB	11	10	12.2	12.2		
683+15	EB	11	20	24.4		24.4	
683+15	WB	11	20	24.4		24.4	
694+60	EB	11	20	24.4		24.4	
694+60	WB	11	20	24.4		24.4	
695+60	EB	11	10	12.2	12.2		
695+60	WB	11	10	12.2	12.2		
696+40	EB	11	6	7.3	7.3		
696+40	WB	11	6	7.3	7.3		
697+70	EB	11	12	14.7	14.7		
697+70	WB	11	6	7.3	7.3		
699+20	EB	11	10	12.2	12.2		
699+20	WB	11	10	12.2	12.2		
700+60	EB	11	6	7.3	7.3		
700+60	WB	11	6	7.3	7.3		
701+05	EB	11	6	7.3	7.3		
701+05	WB	11	6	7.3	7.3		
701+45	EB	11	6	7.3	7.3		
712+40	EB	11	15	18.3		18.3	
712+40	WB	11	15	18.3		18.3	
712+70	EB	11	6	7.3	7.3		
714+30	EB	11	8	9.8	9.8		
716+90	WB	11	6	7.3	7.3		
718+40	EB	11	8	9.8	9.8		
729+95	EB	11	6	7.3	7.3		
740+30	EB	11	6	7.3	7.3		
755+50	WB	11	6	7.3	7.3		
756+40	EB	11	6	7.3	7.3		
756+40	WB	11	6	7.3	7.3		
763+70	WB	11	6	7.3	7.3		
766+25	EB	11	6	7.3	7.3		
772+60	WB	11	6	7.3	7.3		
774+40	EB	11	20	24.4		24.4	
774+40	WB	11	20	24.4		24.4	
781+15	EB	11	6	7.3	7.3		
781+15	WB	11	6	7.3	7.3		
786+10	WB	11	6	7.3	7.3		
789+95	WB	11	6	7.3	7.3		
795+95	EB	11	6	7.3	7.3		
795+95	WB	11	6	7.3	7.3		
805+30	WB	11	6	7.3	7.3		
854+50	NB	12	6	8.0	8.0		
854+50	SB	12	6	8.0	8.0		
874+05	SB	12	10	13.3	13.3		
915+70	EB	18	6	12.0	12.0		
922+40	EB	15	6	10.0	10.0		
922+40	WB	15	6	10.0	10.0		
922+90	WB	12	8	10.7	10.7		
SUBTOTAL =					377.6	183.3	0.0
ADDITIONAL 15% =					434.2	210.8	0.0
TOTAL (B) =					435	211	0
TOTAL (A + B) =					958	240	197

FILE NAME =	USER NAME = chollandeske	DESIGNED -	REVISED -
et:\pw\work\pmdot\chollandeske\0115523\0876E88-sh1-plan_overview.dgn		DRAWN -	REVISED -
	PLOT SCALE = 100.0000' / 1in.	CHECKED -	REVISED -
	PLOT DATE = 3/22/2013	DATE -	REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: N/A SHEET NO. 2 OF 8 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
103	(23,24)RS-4	ST. CLAIR	54	12
CONTRACT NO. 76E88				
ILLINOIS FED. AID PROJECT				