

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTR. CODE	
				ROADWAY 0001 URBAN	100% STATE
61100605	MISCELLANEOUS CONCRETE	CU YD	16.5	16.5	
66500105	WOVEN WIRE FENCE, 4'	FOOT	173	173	
<del>66600105</del>	<del>FURNISHING AND ERECTING RIGHT OF WAY MARKERS</del>	<del>EACH</del>	<del>30</del>	<del>30</del>	
66900200	NON-SPECIAL WASTE DISPOSAL	CU YD	27,475	27,475	⚠
<del>66900400</del>	<del>SPECIAL WASTE GROUNDWATER DISPOSAL</del>	<del>GALLON</del>	<del>0</del>	<del>0</del>	
66900450	SPECIAL WASTE PLANS AND REPORTS	L SUM	1	1	
66900530	SOIL DISPOSAL ANALYSIS	EACH	2	2	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	16	16	
67100100	MOBILIZATION	L SUM	1	1	
67201100	SEALING ABANDONED MONITORING WELLS	EACH	3	3	
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1	
Z0013300	CONCRETE REMOVAL (SPECIAL)	SO YD	1,479	1,479	
Z0013796	SEDIMENT CONTROL, STABILIZED CONSTRUCTION ENTRANCE	SO YD	500	500	
Z0056100	SAND DRAINAGE BLANKET	CUYD	13890	13890	⚠
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1	
Z0065200	SHOT ROCK	TON	3,159	3,159	
<del>Z0076600</del>	<del>TRAINEES</del>	<del>HOUR</del>	<del>0</del>	<del>0</del>	
+ Z0076602	TRAINEES (SPECIAL)	HOUR	2,000	2,000	

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTR. CODE	
				ROADWAY 0001 URBAN	100% STATE
+ Z0076604	TRAINEES TRAINING PROGRAM GRADUATE	HOUR	2,000	2,000	
X0324045	SEDIMENT CONTROL, STABILIZED CONSTRUCTION ENTRANCE REMOVAL	EACH	2	2	
* X0325391	EXPANDED POLYSTYRENE FILL	CUYD	5,740	5,740	⚠
X0324775	SEDIMENT CONTROL, STABILIZED CONSTRUCTION ENTRANCE MAINTENANCE	SO YD	500	500	
X0325833	WICK DRAINS	FOOT	313,758	313,758	⚠
X2010507	CLEARING, SPECIAL	ACRE	32.2	32.2	
X2020410	EARTH EXCAVATION (SPECIAL)	CU YD	100	100	
X4402400	CURB REMOVAL (SPECIAL)	FOOT	78	78	
X5012502	CONCRETE REMOVAL (SPECIAL)	CU YD	465	465	
X6020084	MANHOLE, SPECIAL	EACH	12	12	
X6024240	INLETS, SPECIAL	EACH	17	17	
X7010216	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	1	

+ 0042

⚠ REVISED 6-5-13

**Farnsworth**  
GROUP, INC.  
2709 McFraw Drive  
Bloomington, Illinois 61704  
309/803-8435 309/803-1971 fax

DESIGNED - JUO  
DRAWN - JUO  
CHECKED - PJM  
DATE - 10/18/12

REVISIONS  
REVISIONS  
REVISIONS  
REVISIONS

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.P. RTE. 788	SECTION 520-1-2-1	COUNTY ST. CLAIR	TOTAL SHEETS 121	SHEET NO. 5
ILLINOIS FED. AID PROJECT			CONTRACT NO. 76F70	